

Name of Road: sinwara house of bindhe yadav to sinwara kamattol house of hit kumar kamat.


Block : benipatti District: MADHUBANI Length : 1.000 KM

Sr No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching in slope or apron including including light ramming etc. all complete as per approved design, specification and direction of E/I (Brick Bats)								
		Ch.(KM)								
					$(0.75+1.50)/2$	$(0.60+1.20)/2$				
		0.60	1	60.00	1.125	0.9 0.8	60.75		54.043	
					$(0.10+2.00)/2$	$(0.80+1.60)/2$				
		0.70	2	15.00	1.05	1.20	37.80			
					$(0.70+1.4)/2$	$(0.50+1.00)/2$				
		0.180	1	30.00	1.05	0.75	23.63			
					$(0.60+1.20)/2$	$(0.70+1.40)/2$				
		0.250	1	50.00	0.90	1.05 1.2	47.25		42.75	
					$(0.70+1.40)/2$	$(0.60+1.20)/2$				
		0.400	2	30.00	1.05	0.90	56.70			
					$(1.00+2.00)/2$	$(0.75+1.50)/2$				
		0.600	1	40.00	1.50	1.13 1.0	67.50		60.043	
					$(0.75+1.50)/2$	$(0.45+0.9)/2$				
		0.700	1	10.00	1.13	0.68	7.59			
					$(0.65+1.30)/2$	$(0.25+0.50)/2$				
		0.750	1	12.00	0.98	0.38	4.39			
					$(0.75+1.50)/2$	$(0.55+1.10)/2$				


	0.800	1	50.00	1.13	0.83	46.41			
				$(0.8+1.6)/2$	$(0.70+1.40)/2$				
	0.920	2	80.00	1.20	1.05	201.60			9,99,008.00
						534.87	553.61	Cum	1867.76
									1034015
								TOTAL	1034015

$[534.87 \times 1063 \times 107.4] -$ GST@12% = 119881.00 124082
 LAB. CESS@1% = 9990.00 10340
 SF = 58849
 TOTAL = 1227286

Sum Rs 11,85,736 = 00.


 JE
 RWD BENIPATTI


 AE
 RWD BENIPATTI



 EE
 RWD BENIPATTI

Rs 11,85,736/-

कार्यपालक अधिकारी द्वारा कार्य विह काम प्रसंग में प्रेषित
 प्रमाण-01 कार्य प्रमाण/दिनांक: 10.05.2021 / के द्वारा प्रमाणित
 गौरव अधिकारी के आवास पर

Post fact to TTA, Rs 11,85,736 = 00

प्रेषित दस्तावेज ~~हजार~~ eighty five thousand seven hundred
 thirty six only.


 13.05.21
 Superintending Engineer
 RWD, Works Circle, Darbhanga
 13/05/2021