

# RURAL WORKS DEPARTMENT



## GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM MIRZAPUR TO  
HARIZAN TOLA

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

### ESTIMATED COST

~~5107915.00~~

4822082=0

Inspection Report for flood damage work

Date: 6/11/2020

1. Name of PIUs- Executive Engineer, RWD. Works Division - Farbagani

2. Name of Block/Road- Farbagani  
Mirza Jaur to Harigan taluk.

A. For Road

1. Damage Location/Chainage :

2. Damage Length : 166.0m.

3. Nature of Damage : Road width work out.

4. Details of Restoration :

i Material being used in Restoration

: Local Sand, bamlonpile, Ecloge.  
Asphalt etc.

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

: Restore the damaged part by the  
above material.

iv Restored Length

: 166.0m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

Signature

(Name of Inspector)

कार्यपालक अभियंता का कार्यालय,  
ग्रामीण कार्य विभाग कार्य प्रमंडल फारबिसगंज।

पत्रांक 811 फारबिसगंज/

दिनांक 02/05/2020

प्रेषक,

कार्यपालक अभियंता  
ग्रामीण कार्य विभाग  
कार्य प्रमंडल, फारबिसगंज।

सेवा में,

संबंधित सभी संवेदक  
FMGSY/MMGSY/NABARD

विषय-

प्रधानमंत्री ग्राम सड़क योजना अन्तर्गत निर्माणधीन पुलों के पास उचित संख्या में  
हयूम पाइप देकर डायवर्सन बनाने के संबंध में।

प्रसंग-

जिला पदाधिकारी अररिया का स्थापक 1841/सी0 एवं 1842/सी0 दिनांक-  
02.05.2020

महाराज

उपर्युक्त प्रसांगिक पत्र के आलोक में कहना है कि संभावित बाढ़ वर्ष 2020 की पूर्व  
तैयारियों के मद्देनजर जिला पदाधिकारी अररिया के द्वारा निर्माणधीन सभी पुलों के पास  
आवागमन बहाल रखने हेतु उचित पैदाई के साथ मजबूत डायवर्सन उचित संख्या में  
हयूम पाइप देकर दिनांक 18.05.2020 तक पूर्ण करने का निर्देश प्राप्त हुआ है।

अतः आप सभी संबंधित संवेदकों को निर्देश दिया जाता है कि अपने  
कनीय/सहायक अभियंता से सम्पर्क स्थापित करते हुए दिनांक 15.05.2020 तक  
अपने-अपने पुलों के पास डायवर्सन बना कर इस कार्यालय को सूचित करें तथा वर्ष  
2020 में पुरी वर्षात पथों में सुगम आवागमन बहाल रखने एवं डायवर्सन में किसी प्रकार की  
त्रुटी होने पर पुनः ठीक करने की पूर्ण जबाबदेही आपकी होगी। डायवर्सन बनाते समय  
भारत सरकार द्वारा जारी महामारी Covid -19 का निर्धारित Guide Line का पूर्ण  
रूपेण अनुपालन करना सुनिश्चित करेंगे।

कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल, फारबिसगंज।

स्थापक 811 फारबिसगंज/दिनांक 02/05/2020

प्रतिलिपि-सभी कनीय अभियंता/सहायक अभियंता को निर्देश दिया जाता है कि अपने अपने क्षेत्राधीन  
निर्माणधीन पुलों के पास संबंधित संवेदकों से सम्पर्क स्थापित कर उचित डायवर्सन बनवाना सुनिश्चित की  
जाए।

कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल, फारबिसगंज।

स्थापक 811 फारबिसगंज/दिनांक 02/05/2020

प्रतिलिपि-अधीक्षक अभियंता ग्रामीण कार्य विभाग कार्य प्रमंडल फारबिसगंज, मुख्य अभियंता-2 ग्रामीण कार्य  
विभाग, पटना/ जिला पदाधिकारी अररिया / सचिव ग्रामीण कार्य विभाग, बिहार पटना को सूचना एवं  
आव यक कार्रवाई हेतु समर्पित।

विरासतमाजन

कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल, फारबिसगंज।

## Abstract of Cost

**Name of Work :** Estimate for Repairing/Restoration/Making Motorable Roads  
Damaged during flood in JULY 2019 in ARARIA District

**Name of Road:**

**RESTORATION OF ROAD FROM MIRZAPUR TO HARIZAN TOLA**

**Block:** FORBESGANJ

**District:** ARARIA

**Divison :** RWD, Works Division, FORBESGANJ

**Circle:** RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	2787.23	627.77	1749745.82
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	2988.00	75.86	226665.50
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	996.00	40.06	39900.33
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	51249.60	37.35	1914004.42
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				



		Cum	224.10	1851.91	415013.84
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	40.00	5382.71	215308.30
	TOTAL AMOUNT =				<del>43059.30</del> 4560638.00
	ADD 12.00 %GST=				<del>517652.00</del> 547277.00
	SAY TOTAL AMOUNT =				<del>5107915.00</del>

4822082=10

*[Signature]*  
JE 06/11/20

RWD WORKS  
DIV.  
FORBESGANJ

*[Signature]*  
AE

RWD WORKS DIV. FORBESGANJ

*[Signature]*

RWD WORKS  
DIV. FORBESGANJ

RS 4822082=10

Technically approved for ~~(fifty one Lacs seven thousand nine hundred fifteen Rupees only)~~ ~~Fifty eight Lacs twenty two thousand eighty two RS) only.~~

*[Signature]*

Superintending Engineer  
Rural Works Department  
Works Circle, Kishanganj