

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- SIMARBANNI DHARMANAND MANDAL TO
GANGA RISHIDEV TOLA

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

ESTIMATED COST

999438.00

Inspection Report for flood damage work

Date:

1. Name of PIUs- *RWD WORK DIVISION Furberga*

2. Name of Block/Road- *Bhargama/Simarbani alhanna near market to
Changga Rikher talq.*

A. For Road

1. Damage Location/Chainage :

2. Damage Length : *30 m*

3. Nature of Damage : *side cutting*

4. Details of Restoration :

i Material being used in Restoration :

local sand, B/Bat, Baulso

ii Equipment/Tools being used in Restoration works:

pile, cc bags

iii Procedure taken up in Restoration works :

Tractor, TCB, laborer

iv Restored Length :

30 m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

NA

Sign

[Signature]
06/11/20

[Signature]

Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads Damaged during flood in 2020 in ARARIA District

Name of Road:

Block: BHARGAMA

SIMARBANNI DHARMANAND MANDAL TO GANGA RISHIDEV TOLA
District: ARARIA

Division : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, KISHANGANJ

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	435.00	627.77	273079.95
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	696.00	75.86	52798.56
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	174.00	40.06	6970.44
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Per Bags	12801.69	37.35	478143.03
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	43.50	1870.43	81363.71
TOTAL AMOUNT =					892355.68
ADD 12.00 %GST=					107082.68
SAY TOTAL AMOUNT =					999438.37
					999438.00

[Signature]
JE

RWD SUB DIVISION-FORBESGANJ

AE
RWD SUB DIV.
FORBESGANJ

EE
RWD WORKS DIV. FORBESGANJ

Technically Approved Rs. 999438.00 (Nine lakhs ninety nine thousand
four hundred thirty eight only)

[Signature]
SE
KISHANGANJ
30/11/20

कार्यपालक अभियंता का कार्यालय,
ग्रामीण कार्य विभाग कार्य प्रमंडल फारबिसगंज।

पत्रांक ६११ फारबिसगंज /

दिनांक 02/05/2020

प्रेषक,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, फारबिसगंज।

सेवा में,

संबंधित सभी संवेदक
PMGSY/MMGSY/NABARD

विषय:-

प्रधानमंत्री ग्राम सड़क योजना अन्तर्गत निर्माणधीन पुलों के पास उचित संख्या में
ह्यूम पाइप देकर डायवर्सन बनाने के संबंध में।

प्रसंग:-

जिला पदाधिकारी अररिया का ज्ञापांक 1841/सी0 एवं 1842/सी0 दिनांक-
02.05.2020

महाराज

उपर्युक्त प्रसांगिक पत्र के आलोक में कहना है कि संभावित बाढ़ वर्ष 2020 की पूर्व
तैयारियों के मद्देनजर जिला पदाधिकारी अररिया के द्वारा निर्माणधीन सभी पुलों के पास
आवागमन बहाल रखने हेतु उचित उँचाई के साथ मजबूत डायवर्सन उचित संख्या में
ह्यूम पाइप देकर दिनांक 15.05.2020 तक पूर्ण करने का निर्देश प्राप्त हुआ है।

अतः आप सभी संबंधित संवेदकों को निर्देश दिया जाता है कि अपने
कनीय/सहायक अभियंता से सम्पर्क स्थापित करते हुए दिनांक 15.05.2020 तक
अपने-अपने पुलों के पास डायवर्सन बना कर इस कार्यालय को सूचित करें, तथा वर्ष
2020 में पुरी वर्षात पथों में सुगम आवागमन बहाल रखने एवं डायवर्सन में किसी प्रकार की
त्रुटी होने पर पुनः ठीक करने की पूर्ण जबाबदेही आपकी होगी। डायवर्सन बनाते समय
भारत सरकार द्वारा जारी महामारी Covid -19 का निर्धारित Guide Line का पूर्ण
रूपेण अनुपालन करना सुनिश्चित करेंगे।

६० -

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, फारबिसगंज।

ज्ञापांक ६११ फारबिसगंज / दिनांक 02/05/2020

प्रतिलिपि:-सभी कनीय अभियंता/सहायक अभियंता को निर्देश दिया जाता है कि अपने अपने क्षेत्राधीन
निर्माणधीन पुलों के पास संबंधित संवेदकों से सम्पर्क स्थापित कर उचित डायवर्सन बनवाना सुनिश्चित की
जाए।

६० -

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, फारबिसगंज।

ज्ञापांक ६११ फारबिसगंज / दिनांक 02/05/2020

प्रतिलिपि:-अधीक्षण अभियंता ग्रामीण कार्य विभाग कार्य अंचल किशनगंज, मुख्य अभियंता-2 ग्रामीण कार्य
विभाग, पटना / जिला पदाधिकारी अररिया / सचिव ग्रामीण कार्य विभाग, बिहार पटना को सूचनार्थ एवं
आव यक कार्रवाई हेतु समर्पित।

विश्वासभाजन

०२/०५/२०२०

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, फारबिसगंज।