

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM RAMPUR TO
RAMPUR WEST

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

ESTIMATED COST

806794.00

कार्यपालक अभियंता का कार्यालय,
ग्रामीण कार्य विभाग कार्य प्रमंडल फारबिसगंज।

पत्रांक.....६११..... फारबिसगंज/

दिनांक...०२/०५/२०२०

प्रेषक,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, फारबिसगंज।

सेवा में,

संबंधित सभी संवेदक
PMGSY/MMGSY/NABARD

विषय:-

प्रधोनमंत्री ग्राम सड़क योजना अन्तर्गत निर्माणधीन पुलों के पास उचित संख्या में
हयूम पाइप देकर डायवर्सन बनाने के संबंध में।

प्रसंग:-

जिला पदाधिकारी अररिया का ज्ञापक 1841/सी० एवं 1842/सी० दिनांक-
02.05.2020

महाराष्ट्र

उपर्युक्त प्रसांगिक पत्र के आलोक में कहना है कि संभावित बाढ़ वर्ष 2020 की पूर्व
तैयारियों के मद्देनजर जिला पदाधिकारी अररिया के द्वारा निर्माणधीन सभी पुलों के पास
आवागमन बहाल रखने हेतु उचित उंचाई के साथ मजबूत डायवर्सन उचित संख्या में
हयूम पाइप देकर दिनांक 15.05.2020 तक पूर्ण करने का निर्देश प्राप्त हुआ है।

अतः आप सभी संबंधित संवेदकों को निर्देश दिया जाता है कि अपने
कनीय/सहायक अभियंता से सम्पर्क स्थापित करते हुए दिनांक 15.05.2020 तक
अपने-अपने पुलों के पास डायवर्सन बना कर इस कार्यालय को सूचित करें, तथा वर्ष
2020 में पुरी वर्षात पथों में सुगम आवागमन बहाल रखने एवं डायवर्सन में किसी प्रकार की
त्रुटी होने पर पुनः ठीक करने की पूर्ण जबाबदेही आपकी होगी। डायवर्सन बनाते समय
भारत सरकार द्वारा जारी महामारी Covid -19 का निर्धारित Guide-Line का पूर्ण
रूपेण अनुपालन करना सुनिश्चित करेंगे।

६० -

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, फारबिसगंज।

ज्ञापक.....६११..... फारबिसगंज/ दिनांक ०२/०५/२०२०

प्रतिलिपि:-सभी कनीय अभियंता/सहायक अभियंता को निर्देश दिया जाता है कि अपने अपने क्षेत्राधीन
निर्माणधीन पुलों के पास संबंधित संवेदकों से सम्पर्क स्थापित कर उचित डायवर्सन बनवाना सुनिश्चित की
जाए।

६० -

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, फारबिसगंज।

ज्ञापक.....६११..... फारबिसगंज/ दिनांक ०२/०५/२०२०

प्रतिलिपि:-अधीक्षण अभियंता ग्रामीण कार्य विभाग कार्य प्रमंडल फारबिसगंज, मुख्य अभियंता-२ ग्रामीण कार्य
विभाग, पटना/ जिला पदाधिकारी अररिया / सचिव ग्रामीण कार्य विभाग, बिहार पटना को सूचनार्थ एवं
आव यक कार्रवाई हेतु समर्पित।

विश्वासभाजन

०२/०५/२०२०

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, फारबिसगंज।

Inspection Report for flood damage work

Date: 6/11/20

1. Name of PIUs- Executive Engineer, RWD, Works Division - Forbesganj

2. Name of Block/Road- Forbesganj

A. For Road

- Rampur to Rampur West -

1. Damage Location/Chainage :

2. Damage Length : 40.0m

3. Nature of Damage : Slide cutting

4. Details of Restoration :

i Material being used in Restoration

: Local sand, bamboo piles, EC by B/s etc.

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

: Restore the damaged part of road by the above material,

iv Restored Length

: 40.0m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE



Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2019 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM RAMPUR TO RAMPUR WEST

Block: FORBESGANJ

District: ARARIA

Divison : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

SI No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	586.67	627.77	368292.65
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	480.00	75.86	36412.13
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	240.00	40.06	9614.54
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	6992.37	37.35	261142.08
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	24.00	1870.43	44890.39

6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	0.00	5382.71	0.00
	TOTAL AMOUNT =				720352.00
	ADD 12.00 %GST=				86442.00
	SAY TOTAL AMOUNT =				806794.00

[Signature]
JE
06/11/20

RWD WORKS
DIV.
FORBESGANJ

AE

RWD WORKS DIV. FORBESGANJ

E.E.

RWD WORKS
DIV. FORBESGANJ

Technically Approved for Rs 806794.00 (Rupees Eight Lacs Six thousand Seven hundred and Ninety Four) only

[Signature]
Superintending Engineer
Rural Works Department
Works Circle, Kishanganj