

Name of Road: Jhitki to Balarahi

Block : Harlakhi District: MADHUBANI Length : 3.204 KM


Sr No.	Item	Item of Work	No s	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching in slope or apron including including light ramming etc. all complete as per approved design, specification and direction of E/I (Brick Bats)								
		Chainage								
				$(3+5+8)/3$	$(3+2+1.5)/3$	$(2.5+2.9+2.5)/3$				
		730 KM	1	5.33	2.17	2.63	30.43			
					$(4.5+4+4.1)/3$	$(1.5+1.9+1.2)/3$				
			1	17.00	4.20	1.53	109.48			
		1150 KM			$(1.9+1.8+1.5)/3$	$(4.9+4.5+4.1)/3$				
			1	15.00	1.73	4.50	117.00		114.18 MB	
		1210 KM			$(4.5+5+4.5)/3$	$(1.2+4+1.8)/3$				
			1	6.00	4.67	2.33	65.33			
		1240 KM			$(1.2+4.0+1.9)/3$	$(1.2+1.9+2.0)/3$				
			1	15.00	2.37	1.70	60.35			
		1310 KM			$(1.2+2.5+1.9)/3$	$(1.2+3.5+3.1)/3$				
			1	5.00	1.87	2.60	24.27			
		1330 KM			$(2.5+2.9)/2$	$(4.2+4.5+3.7)/3$				
			1	4.00	2.70	4.13	44.64			
		1450 KM			$(4+3+3.2)/3$	$(2.4+2.5+2)/3$				
			1	4.00	3.40	2.30	31.28			
		1470 KM			$(1.9+1.5)/2$	$(3.5+4.0+3.9)/2$				
			1	5.00	1.70	5.70	48.45			
		1480 KM			$(1.9+1.5+1.8)/3$	$(3.5+4.0+3.9)/3$				
			1	14.00	1.73	3.80	92.21		64.18 MB	
			1	4.00	2.00	1.50	12.00			

					632.62 M ³	635.44	Cum	1867.76	1186855
					604.59 M ³		TOTAL		1186855


GST@12%	+ 142423
LAB. CESS@1%	+ 11869
SF	+ 67548
TOTAL	1408694

Add. SF [604.59 M³]
~~632.62~~ X 1063 X 10%] + 67247
 64268

Say Rs 1408694.00
 13,40,296.00



 26.12.20
 JE
 RWD
 HARLAK


 26/12/20
 AE
 RWD
 HARLAKHI


 27.12.21
 EE
 RWD
 BENIPAT

कार्यवाहक अभियंता, शान्ति नगर, कार्यवाहक - बिराटूर का
 पत्र:-348 दिनांक:- 13.04.2021 के द्वारा एनएनई. ऑफिस में
 के आचार पर।

Post-facto T/A Rs. 13,40,296.00
 (Rupees Thirteen lacs forty thousand two hundred ninety
 - six only.)


 13.5.21
 Superintending Engineer
 RWD, Works Circle, Darbhanga
 13/05/2021