



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-	Sakhaura Chowk to Sakhaura Village PMGSY Road		
DISTRICT	Muzaffarpur		
DIVISION	Muzaffarpur East-1		
BLOCK	Bandra		
TOTAL LENGTH OF ROAD	:	1.100	KM
CONSTRUCTION COST	:	4.041	Lac

Submitted By :-
Executive Engineer
RWD Work Division Muzaffarpur East-1

प्रतिवेदन

कार्य का नाम:- सरखौरा चौक से सरखौरा गाँव 17.6.87 पथ तक

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- बन्दरा

वित्तीय वर्ष - 2020-21

प्राक्कलित राशि - Rs. 4.041 लाख

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 4.041 लाख है, कार्य प्रमण्डल मुजफ्फरपुर खर्ची-1, प्रखण्ड बन्दरा में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में ईट टुकड़ा स्थानीय बाधु भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी घटनोत्तर स्वीकृति अपेक्षित है।

Bumr

11.11.2020

कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशासक बन्दरा

क्रि

11.11.2020

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशासक बन्दरा

क्रि

15.12.20

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमण्डल मुज0

पूर्वी-1.

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- EXECUTIVE ENGINEER-RWD(W) DIV. Muzaffarpur East-1
- 2 Name of Block/Road- Banahy, Saklausa chowk to Saklausa village Poree road.

A For Road

- 1 Damage Location/Chainage At every place
- 2 Damage Length 82.75mts
- 3 Nature of Damage Complete traffic block due to breach of road.
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Poree Sat, local sand
 - ii Equipments/Tools being used in Restoration Works- JCB, Tractor, Road roller, manpower
 - iii Procedure Taken up in Restoration Works- Immediate restoration of traffic
 - iv Restored Length 82.75mts

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

Signature of JE/ AE/ EE


Signature
(Name of Inspector)

GENERAL ABSTRACT

Name of Road Sakhaura Chowk to Sakhaura Village PMGSY Road

District Muzaffarpur

Block Bandra

Division Muzaffarpur East-1

Length of Road (in Km) 1.100 Km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Jhama metal	3.791
2	Sand Filling	0.250
3	H.P.	0.000
4	Bamboo Piles	0.000
	GRAND SUB TOTAL	4.041
TOTAL COST OF PROJECT IN LACS =		4.041

Sum
11.11.2024
JE
RWD

18.11.2024
11.11.2024
AE
RWD

15.12.20
EE
RWD

Technically approved for Rs. 404/00 = (Rs. Four hundred four thousand one hundred) only.

18.12.20
SE, RWD
Notes: Circle, Muzaffarpur

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Jhama metal Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi making and maintaining diversion light barrier - do - do- danger signal etc. all complete .				
			Appendix - I	Cum	186.45		
			Total	Total	186.45	2033.34	379116.24
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9				
			Appendix - II	Cum	54.980		
			Total	Total	54.98	454.53	24990.06
Total Cost :-							404106.30

Sumit
11-11-2020
JL

17/11/2020
11-11-2020
A.C.

15/12-20
ETC