

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधुबनी।
पत्रक - 1259313

दिनांक : 25.05.2021

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मधुबनी

अभियंता अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मधुबनी

विषय:- ग्रामीण कार्य विभाग, कार्य प्रमंडल, दरभंगा-2 के अधीन रिकमाडा एव मनीगाछी प्रखंड में वर्ष 2020 में बाट/अविवृष्टि से क्षतिग्रस्त 101 जमी/पुलों में कारगरे मदे पुनरुद्धारण कार्य से संबंधित पथों का प्राकलन के समय में।

प्रस्ताव:- मजदीद का पत्रक-871 अगुठ दिनांक-10.04.2021

महाराज, उपरोक्त विषयक प्रासंगिक पत्र से प्राप्त यातायात पुनरुद्धारण के निम्नांकित प्राकलन को गठित

जीव वल द्वारा जीवोपरान्त आवश्यक कार्रवाई हेतु समितित की जाती है। विवरणी निम्न प्रकार है:-

Sl No	Block	Name of Road	Length (KM)	Qty. (Brick Bats) (M3)	Remarks
1	Manegachhi	Ashek Paper Mill Chakkari to Bideswar Sthan road	9.150	650.160	
2	Manegachhi	PMGSY Path Yashaul to S.H. 67 Bhatpara road	1.970	315.940	
3	Manegachhi	PMGSY Road Yashaul to Mithanahat tola	0.530	351.710	
4	Manegachhi	Tola to Bhatra	1.170	257.390	
5	Manegachhi	Lahoria State Boring to Indrathar H.O. Road tak	1.215	277.840	
6	Manegachhi	PWD Path to Kiyahat tola	1.100	168.340	
7	Manegachhi	PMGSY road to Kiyahat Bhatpara	1.600	73.760	
8	Manegachhi	PWD Patna Baharwa to Kanyas Bhatpara via Yashaul tola	3.240	694.930	
9	Manegachhi	Lahoria R.V. Station to Sonpur via Yashaul road	1.500	171.080	
10	Manegachhi	PWD Path Katma Baharwa to Bhatra tola	1.600	250.920	
11	Manegachhi	Bhatra tola Jagadishpur to Modin tola Jagadishpur	0.770	85.490	
12	Manegachhi	Tola to Bhatra	1.027	103.020	
13	Manegachhi	PWD road Bhatra to PWD road Kanyahat	1.590	519.680	
14	Manegachhi	PMGSY Bhatra to Panchgachhi	1.650	226.500	
15	Manegachhi	R.O. road to Bhatra tola	1.170	444.500	
16	Manegachhi	Upin Majra chack to Amritnagar road	3.800	289.330	
17	Manegachhi	PMGSY Path to Larkur Mahadali tola road	1.330	88.230	
18	Manegachhi	PMGSY road Sakhi to Khatpura Secma	0.500	237.750	
19	Manegachhi	PWD road Bhatra to Kanakpur	1.030	138.520	
20	Manegachhi	PWD Sasaulha Deykghar to Danji Masul tola via Refaral Hospital tak	1.500	638.430	
21	Manegachhi	Tola Brahmapara to Sakhi road	2.440	243.010	
22	Manegachhi	PMGSY Path to Larkur Brahmapara tola	1.050	429.000	
23	Manegachhi	Sakhi tola to School	2.500	559.620	
24	Manegachhi	R.O. road to Khatpura Middle School Chakri tola	1.090	679.100	
25	Manegachhi	Makranda to Bideswar Bhatpara via Athan	3.200	472.180	
26	Manegachhi	PMGSY Sadak to Paswan tola	1.000	286.170	
27	Manegachhi	Prantik Yashaul tola to Mushari H.O. via Yashaul School tak	2.000	481.430	
28	Manegachhi	Manna Bahara Paswan tola to Makranda tola	1.110	341.800	

Estimate of Temporary Restoration of Flood affected Road

Name of Road:- Makranda to Bageshwari Bhagawati Asthan

BLOCK :- Manigachhi

District:- Darbhanga

SUB HEAD : BRICK BATS

Laying & Distribution of Brick bats on affected Road portion as per specification to meet the required slope and proper light Ramming from a specified lead as per direction of E/I.

Sl No	Chainage (in M)		Unit	Nos.	Length (m)	Width (Avg.) (m)	Height / Thickness (Avg.) (m)	Quantity	Rate (In Rs.)	Amount (In Rs.)
	From	To								
	0	100	Cum	1	7.00	4.00	0.30	8.40	1840.16	15457.00
		150	Cum	1	5.00	1.50	0.60	4.50	1840.16	8281.00
			Cum	1	5.00	1.80	0.30	29.70	1840.16	54653.00
		650	Cum	1	16.00	4.00	0.45	28.80	1840.16	52997.00
		750	Cum	1	30.00	5.00	0.90	135.00	1840.16	248422.00
			Cum	1	18.00	4.50	0.45	36.45	1840.16	67074.00
		900	Cum	1	30.00	0.90	0.60	16.20	1840.16	29811.00
			Cum	1	10.00	0.90	0.30	2.70	1840.16	4968.00
		1200	Cum	1	31.00	4.50	0.60	83.70	1840.16	154021.00
			Cum	2	5.00	3.00	0.30	9.00	1840.16	16561.00
			Cum	1	24.00	0.90	0.45	9.72	1840.16	17886.00
			Cum	1	15.00	0.90	0.45	6.08	1840.16	11179.00
		1500	Cum	1	31.00	5.00	0.90	139.50	1840.16	256702.00
			Cum	1	8.00	1.80	0.50	7.20	1840.16	13249.00
			Cum	1	6.00	1.80	0.45	4.86	1840.16	8943.00
		1650	Cum	1	31.00	4.50	0.45	62.78	1840.16	115516.00
			Cum	1	14.00	4.00	0.45	25.20	1840.16	46372.00
		1800	Cum	1	5.00	4.00	0.45	9.00	1840.16	16561.00
			Cum	1	19.00	5.00	0.45	42.75	1840.16	78667.00
		1850	Cum	1	6.00	2.50	0.60	9.00	1840.16	16561.00
			Cum	1	30.00	4.00	0.60	72.00	1840.16	132492.00
		2050	Cum	1	45.00	4.00	0.60	108.00	1840.16	198737.00
		2200	Cum	1	9.00	3.50	0.60	18.90	1840.16	34779.00

