

RURAL WORKS DEPARTMENT GOVT. OF BIHAR



Name of Work:- Dumra Dumarpati to Wahailwara.

Block:- Pupri.

F.D.R

Rs. ~~226042.00~~ 220586.00

Year-2020-21

Name of Circle:- R.W.D, Works Circle, Sitamarhi.

Name of Division:- R.W.D., (W) Division, Pupri.

District:-Sitamarhi

S. No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	200037.00
2	Labour Cess @ 1%	2000.37
3	GST @ 12%	24004.44
	Total Cost of Road Repair	226041.81
	Say	226042.00

920586, no

JE

AE
21/12/20

21/12/2011

87-10-19 10.02.21

16/6/21
 16/6/21
 16/6/21

[Handwritten signature]
30.12.2020
3rd Div, Belsund

- 15/11/14
 12/11/14 11/11/14
 10/11/14 9/11/14

~~Technically approved for Rs. 226042.00 (Rupee
Two Lakhs twenty six thousand and forty two) only.
Technically approved for Rs. 120586.00 (Rupee
One hundred and twenty thousand and six only)~~

12/5/21

Schedule of Quantity

name of Road:- Dumra Dumarpati to Wahailwara.

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	401.00	0.00
2	Providing and laying of Brick Bat obtained from Chimney with machanical means with all spreading, grading to required slope and compacted at OMC to achieve required density with all complete as per the direction of engineer in charge.	144.4100 140.925 08.185			0.00
	Less 20% for Voids	28.882			1749296.04
		115.5280	Cum	1546.00	178606.288
3	Single bamboo paaisiding/ walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half or tying with wire complete and Struts 1.5m apart longitudinally and providing brush wood as per drawing and technical specification clause 1302.5	0.00	m	172.62	0.00
4	Providing, Laying and placing empty cement bag filled with local sand including stitching with sutall etc. do.....do.....all complete job as per specification and direction of E/L. (including Royalty and all Taxes)	0.00	no.	23.12	0.00
5	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row with old available pipe	0.00	m	3158.69	0.00
6	Providing Quarry Material Rabbish for filling the voids in bricks batsdo.....all complete job as per specification and direction of E/L.	98.185			90913.27
	Taking 20% of Brick Qty for Rabbish	28.882	Cum	742.00	21430.444
				Total	200036.732
				Say	200037.00
					195209.10

21.12.20
21.12.20

AE
21/12/20

JE
21/12/20

Details of Measur of ditches filled by brick bats and rabbish				
Name of Road:- Dumra Dumarpati to Wahailwara.				
	L	W	H	VOLUME
At 300 M	12.50	2.000	0.7750	19.3750
At 900 M	21.00	1.700	0.2500	8.9250
At 1900 M	34.00	10.250	1.5000	522.7500
				551.0500
Deduction	34.00	9.200	1.3000	406.6400
				144.4100
Laying Hume Pipe of 1000 mm dia	0	0	0	0.00
Cement Bage				

28/11/20
 28/11/20
 RWD Beland.

21/11/20
 AC

21/11/20

21/11/20

522.7500
 551.0500
 406.6400
 144.4100

UT DATA
DISTRICT
HABITATION CODE
BLOCK
ROAD DETAILS
From (Chainage)
To (Chainage)
Flush Drain (Cum)
Road Connecting To
Brick Soling for Dismantling
CC Road for Dismantling
BT Road for Dismantling
Format 2 B : CD's
CD Details

Name of the Road
Existing CD:

Flush Clauseway
HP Culvert 1 Row
HP Culvert 2 Row
HP Culvert 3 Row
HP Culvert 4 Row
0.5m Span Slab Culvert
1.0m Span Slab Culvert
1.50m Span Slab Culvert
2m Span Culvert
3m Span Culvert
4m Span Culvert
5m Span Culvert
6m Span Culvert
2x6m Span Slab Culvert
Vented Clauseway
Below 600mm Dia Culvert
Bridge
Prepared By

Works Division, Pupri.

Name of Road:- Dumra Dumarpati to Wahailwara.
Nos

Sitamathi
Pupri
Name of Road:- Dumra Dumarpati to Wahailwara.
0.30km
1.90KM
3.0km