

1



ग्रामीण कार्य विभाग

पथ का नाम :- R-40 सड़क से फुलवारीगढ़ पथ ।

कार्य प्रमण्डल :- बेनीपुर ।

कार्य अंचल :- दरभंगा ।

प्रखण्ड का नाम :- त. रडोह ।

प्राक्कलित राशि :- 4,24,914/-
₹ 4,03,877/-

Abstract of Govt.

प्रतिवेदन


पथ का नाम :- R.E.O सड़क से फुलपरिगौ तड पथ।
पथ की लं० :- 3.0 KM
प्राक्कलित राशि :- 9 4, 24, 914 =0


यह प्राक्कलन मो०.....1,24,914.....का बनाया गया है। ज्ञातव्य हो कि विगत माह जुलाई-अगस्त 2020 में अतिवृष्टि एवं बाढ़ के कारण तारडीह प्रखण्ड के बहुत से सड़क में टुटान हो गया। विभागीय आदेश -मु० अ०-04(मु०) विविध कार्य 23-40/2016-2729 अनु० दिनांक-21.08.2020 एवं कार्यपालक अभियंता महोदय के आदेश के अनुपालनार्थ यह प्राक्कलन बनाया गया है। प्राक्कलन में सड़क की अधिक गड्ढी खाई में मिट्टी भरकर तदनुपरान्त ईट टुकड़ा की एक समुचित परत डाल कर यातायात सुलभ हेतु मजबुतीकरण की गई है। फलैंक में क्रॉस पाइलिंग के उपरान्त सीमेंट की खाली बोरी में स्थानीय बालू भरकर सीमेंट कंक्रीट सड़क को बचाने का काम किया गया है।

प्राक्कलन वर्तमान में कार्य अंचल दरभंगा की अनुसूचित दर पर तैयार किया गया है।

प्राक्कलन की स्वीकृति कार्य हीत एवं जनहीत में अपेक्षित है।


कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा तारडीह


सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल तारडीह,


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग
कार्य प्रमण्डल बेनीपुर

Abstract of Cost.

1. पथ का नाम :- R.E.O रुद्रक री कुलवारिओं तड पथ।
2. प्राक्कलित राशि :- 4,24,914 = 0
3. कार्य प्रमण्डल :- बेनीपुर।
4. प्रखण्ड :- तारडीह।

i. Providing and laying reinforced cement concrete pipe NP3 etc. 600 A.M. ५.
 50.8 9.3 do.....do.....all complete job.

5M @ Rs 2629.73/Mtr ————— Rs 13,148 = 65

ii. Providing and laying of brick bats in with carriage by tractor loading with front end loader with light ramming etc all complete jobs as per specifications and direction of E/I.

187-6/M³ @ Rs 1840-16/M³ ————— Rs 327,521.00
 177.985 M³ ————— Rs 324,232.44
 Add U.S.T 12 + ————— Rs 146,880.00
 Add I.T. L.C ————— Rs 43,005.72
 Add S.F. (187-61 X 1063 X 101) = 177.985 ————— Rs 3,742.94
 Total Rs 4,24,914 = 0

(Signature)
 JE

RWD, Work section
 Tardih.

(Signature)
 AE

RWD, Works Sub division
 Tardih.

(Signature)
 EE

RWD, Works Division
 Benipur.

कार्यपालक अभियंता, ग्राम कार्य विभाग, कार्यप्रमण्डल-अवतार का पथ- 798 2130/
 दिनांक-07.04.2021 के द्वारा स्वीकृत-अध्यक्ष अभियंता के आचार्य 42-

Post - Ferto T/A 798 2130 4,03,877 = 00 (Rupees Four Lacs -
 Three thousand eight hundred seventy seven only.)

(Signature)
 09.04
 Superintending Engineer
 RWD, Works Circle, Darbhanga
 09/04/2021

पथ का नाम - R.C.C सड़क री फुलवरीया नु पथ - 3.0 KM

खोड का नाम - (नारदीह)

Flood damage Road estimate dated - 2020.

Items of work			Qty.
Providing and laying R.C.C hume pipe (H ₃ 600mm) dia reinforcement concrete pipe for culvert in cut part work. do. do all complete job as per B/L			
Chainage (m)	Length (m)	Measurement details.	
0	—	—	
1100M	5M	2 nos x 2.50M = 5M R.C.C hume pipe (600mm) ∴ Qty = 5M	5M
Providing and laying of Brick bats with carriage by tractor loading with front end loader with slight Ramping etc all complete job as per B/L			
Chainage (m)	Length (m)	Measurement details.	
3500M	10.60M	$10.60M \times \left(\frac{0.90 + 0.75}{2} \right) \times 0.15M (Av) = 1.31M^3$	
500M	9M Flank.	$2 \times 9M \times \left(\frac{1.1 + 1.20}{2} \right) \times \left(\frac{0.60 + 0.30}{2} \right) = 8.91M^3$	
	28M	$2.8M \times \left(\frac{3.0 + 2.80 + 3.30}{3} \right) \times \left(\frac{0.7 + 0.6 + 0.5}{3} \right) \times 0.60M (Av) = 50.95M^3$	
600M	10M	$2 \times 10M \times 1M \times 0.20M (Av) = 4.0M^3$	
	2M	$2 \times \left(\frac{1.40 + 1.20}{2} \right) \times 0.20M (Av) = 0.52M^3$	
	2.10M	$2.10M \times \left(\frac{0.90 + 0.80}{2} \right) \times 0.25M (Av) = 0.44M^3$	
900M	8M	$8M \times \left(\frac{3 + 2.90}{2} \right) \times 0.15M (Av) = 3.54M^3$	
1100M CWS	30M	$15M \times \left(\frac{3.40 + 3.20}{2} \right) \times 0.90M (Av) = 3.47.02M^3$ $15M \times \left(\frac{3.20 + 3.50}{2} \right) \times 1.30M (Av) = 65.32M^3$	
1500M	8.90M	$8.90M \times \left(\frac{1.30 + 0.90}{2} \right) \times 0.60M (Av) = 5.60M^3$ Qty = 187.61M ³	187.61M ³

(Signature)
J.E

(Signature)
A.E

(Signature)
C.E

Physically verified and corrected as per site

(Signature)
27.04.21
A.E

(Signature)
21/4

F.D.R. - 2020-21

पथ का नाम - R.E.O. सड़क रो फुलवारीयों तक पथ - 3.0KM
खोजक का नाम - (ताडीर)

Flood Damage Road estimate dated 1-2020.

S.NO	ITEMS OF WORK	Qty.																																	
[1]	Providing and laying R.C.C. hume pipe (600mm) dia reinforcement concrete pipe for culvert in cuts part work. do. do. all complete job as per e/L																																		
	<table border="1"> <thead> <tr> <th>Chainage</th><th>Length (m)</th><th>Measurement details.</th></tr> </thead> <tbody> <tr> <td>0</td><td>—</td><td>—</td></tr> <tr> <td>1100M</td><td>5M</td><td> $2NOS \times 2.50M = 5M \text{ R.C.C. hume pipe (600mm)}$ $\therefore \text{Qty} = 5M$ </td></tr> </tbody> </table>	Chainage	Length (m)	Measurement details.	0	—	—	1100M	5M	$2NOS \times 2.50M = 5M \text{ R.C.C. hume pipe (600mm)}$ $\therefore \text{Qty} = 5M$	5M																								
Chainage	Length (m)	Measurement details.																																	
0	—	—																																	
1100M	5M	$2NOS \times 2.50M = 5M \text{ R.C.C. hume pipe (600mm)}$ $\therefore \text{Qty} = 5M$																																	
[2]	Providing and laying of Brick bats with carriage by tractor loading with front end loader with light ramming etc all complete job as per e/L																																		
	<table border="1"> <thead> <tr> <th>Chainage</th><th>Length (m)</th><th>Measurement details.</th></tr> </thead> <tbody> <tr> <td>3500M</td><td>10.60M</td><td>$10.60M \times \left(\frac{0.90 + 0.75}{2}\right) \times 0.15M (Av) = 1.31M^3$</td></tr> <tr> <td>500M</td><td>9M</td><td>$2 \times 9M \times \left(\frac{1 + 1.20}{2}\right) \times \left(\frac{0.60 + 0.30}{2}\right) = 8.91M^3$</td></tr> <tr> <td></td><td>28M</td><td>$28M \times \left(\frac{3.0 + 2.80 + 3.30}{3}\right) \times \left(\frac{0.7 + 0.6 + 0.5}{3}\right) \times 0.60M (Av) = 50.95M^3$</td></tr> <tr> <td>600M</td><td>10M</td><td>$2 \times 10M \times 1M \times 0.20M (Av) = 4.0M^3$</td></tr> <tr> <td></td><td>2M</td><td>$2 \times \left(\frac{1.40 + 1.20}{2}\right) \times 0.20M (Av) = 0.52M^3$</td></tr> <tr> <td></td><td>2.10M</td><td>$2.10M \times \left(\frac{0.90 + 0.80}{2}\right) \times 0.25M (Av) = 0.44M^3$</td></tr> <tr> <td>900M</td><td>8M</td><td>$8M \times \left(\frac{3 + 2.90}{2}\right) \times 0.15M (Av) = 3.54M^3$</td></tr> <tr> <td>1100M</td><td>30M</td><td> $15M \times \left(\frac{3.40 + 3.20}{2}\right) \times 0.95M (Av) = 39.60M^3$ $15M \times \left(\frac{3.20 + 3.50}{2}\right) \times 1.30M (Av) = 65.32M^3$ </td></tr> <tr> <td>1500M</td><td>8.90M</td><td>$8.90M \times \left(\frac{1.20 + 0.90}{2}\right) \times 0.60M (Av) = 5.60M^3$</td></tr> <tr> <td></td><td></td><td> $\text{Qty} = 187.61M^3$ $180.75M^3$ </td></tr> </tbody> </table>	Chainage	Length (m)	Measurement details.	3500M	10.60M	$10.60M \times \left(\frac{0.90 + 0.75}{2}\right) \times 0.15M (Av) = 1.31M^3$	500M	9M	$2 \times 9M \times \left(\frac{1 + 1.20}{2}\right) \times \left(\frac{0.60 + 0.30}{2}\right) = 8.91M^3$		28M	$28M \times \left(\frac{3.0 + 2.80 + 3.30}{3}\right) \times \left(\frac{0.7 + 0.6 + 0.5}{3}\right) \times 0.60M (Av) = 50.95M^3$	600M	10M	$2 \times 10M \times 1M \times 0.20M (Av) = 4.0M^3$		2M	$2 \times \left(\frac{1.40 + 1.20}{2}\right) \times 0.20M (Av) = 0.52M^3$		2.10M	$2.10M \times \left(\frac{0.90 + 0.80}{2}\right) \times 0.25M (Av) = 0.44M^3$	900M	8M	$8M \times \left(\frac{3 + 2.90}{2}\right) \times 0.15M (Av) = 3.54M^3$	1100M	30M	$15M \times \left(\frac{3.40 + 3.20}{2}\right) \times 0.95M (Av) = 39.60M^3$ $15M \times \left(\frac{3.20 + 3.50}{2}\right) \times 1.30M (Av) = 65.32M^3$	1500M	8.90M	$8.90M \times \left(\frac{1.20 + 0.90}{2}\right) \times 0.60M (Av) = 5.60M^3$			$\text{Qty} = 187.61M^3$ $180.75M^3$	187.61M ³
Chainage	Length (m)	Measurement details.																																	
3500M	10.60M	$10.60M \times \left(\frac{0.90 + 0.75}{2}\right) \times 0.15M (Av) = 1.31M^3$																																	
500M	9M	$2 \times 9M \times \left(\frac{1 + 1.20}{2}\right) \times \left(\frac{0.60 + 0.30}{2}\right) = 8.91M^3$																																	
	28M	$28M \times \left(\frac{3.0 + 2.80 + 3.30}{3}\right) \times \left(\frac{0.7 + 0.6 + 0.5}{3}\right) \times 0.60M (Av) = 50.95M^3$																																	
600M	10M	$2 \times 10M \times 1M \times 0.20M (Av) = 4.0M^3$																																	
	2M	$2 \times \left(\frac{1.40 + 1.20}{2}\right) \times 0.20M (Av) = 0.52M^3$																																	
	2.10M	$2.10M \times \left(\frac{0.90 + 0.80}{2}\right) \times 0.25M (Av) = 0.44M^3$																																	
900M	8M	$8M \times \left(\frac{3 + 2.90}{2}\right) \times 0.15M (Av) = 3.54M^3$																																	
1100M	30M	$15M \times \left(\frac{3.40 + 3.20}{2}\right) \times 0.95M (Av) = 39.60M^3$ $15M \times \left(\frac{3.20 + 3.50}{2}\right) \times 1.30M (Av) = 65.32M^3$																																	
1500M	8.90M	$8.90M \times \left(\frac{1.20 + 0.90}{2}\right) \times 0.60M (Av) = 5.60M^3$																																	
		$\text{Qty} = 187.61M^3$ $180.75M^3$																																	

Signature

J.E

(1 x 4 m x 5 m)

Less 5M 600mm dia HP

Chasli
12/12/2020

A.F

Take off = 177.98M³

E.F

(D) Supply for Bricks bats (with OH)
 Basic Rate of Bricks bats Rs 1063.10 / 3 1126.78
 Add 6% OH Rs 63.78

(A) Labour for laying Bricks bats / Shama Khar including 10% etc.

Unit = Per M³
 Taking output = 5.832 M³
 Unskilled Haulage = 3 Nos @ 287.10 = Rs 861.30
 6% OH = Rs 51.68
 Rate for 2.832 M³ = Rs 912.66
 Rate per M³ = Rs 322.27

(B) Haulage excluding loading and unloading, packing
Haulage of Materials by Tractor

Unit = t.k.m

Taking output 3.60-tonne load and load 10 km = 36 t.k.m

(i) Surface Road

Speed with load = 15 km/hour

Speed while returning empty = 25 km/hour

(a) Machinery

Tractor 3.6 tonne Capacity 0.667 @ 549.10/hour = Rs 366.24

(b) Time taken for empty return = 0.400 @ 549.10/hour = Rs 219.64

(c) Time taken for empty return = 0.400 @ 549.10/hour = Rs 219.64

(b) Over head (OH) charge 6%

COST for 36 t.k.m

Rate per t.k.m = Rs 17.25

(ii) Katchha Road

Speed with load = 12 km/hour

Speed for empty return trip 20 km/hour

(a) Machinery

Tractor 3.6 tonne Capacity

Time taken for onward haulage with load = 1.00 @ 549.10/hour = Rs 549.10

Time taken for empty return trip = 0.667 @ 549.10/hour = Rs 366.24

(b) OH @ 6%

COST for 36 t.k.m

Rate per t.k.m = Rs 26.95

(C) Loading and unloading Bricks bats / Shama Khar / Sand etc.

Placing tractor at loading point loading with front loader, dumping, turning for return trip, excluding haulage and return trip

Unit = cum / Taking output = 2.25 M³ / Time required 8.70 h

(i) Labour

Rate 0.03 @ 305.20/day = Rs 9.15

Unskilled Labour for loading, unloading 0.72 @ 287/day = Rs 206.64

(ii) Machinery

Tractor 3.6 t Capacity 0.1 @ 549.10/hour = Rs 54.91

Front end loader 1 cum bucket 0.083 @ 1403.00/h = Rs 116.45

2.25 cum/h Capacity 0.083 @ 1403.00/h = Rs 116.45

(iii) Over head (OH) = 6%

COST for 2.25 M³ = Rs 410.58

Rate per M³ = Rs 182.39

[illegible]

Admission 1000/1000

1

Total Rs. 1867.76 [without GST + 10 + 5%]
P.H.S.

Folio R^a 1840.16 p^m3 [noted as ...]

7072 P 1812 56. P 1812 (1812) 1812

Total Wt of Brick bats $\text{sqm}^2 = 112.678 + 335.9 = 448.578$

Total cost of Buick Buick = $1126.48 + 908.31 = 2034.79$

12.11.2019

पथ का नाम : REO रोड से फुलवरिया




JE
Tardik


AE
Tardik

EE
Rind, Benipur

पत्र का नाम :- REO रोड से पुलवरिया




JE
RWD, Benipur
(Tardh)


AE
RWD, Benipur
(Tardh)


EE
RWD, Benipur

पथ का नाम — REO रोड से जुलाहा



31
RwD, Benipur
(Tardik)

Phulbi
12/12/20
AE
RwD, Benipur
(Tardik)

EE