



ग्रामीण कार्य विभाग

पथ का नाम :- टी० १ है मुर्मुजापुर
कार्य प्रमण्डल :- बेनीपुर।
कार्य अंचल :- दरभंगा।
प्रखण्ड का नाम :- बेनीपुर।
प्राक्कलित राशि :- Rs. ~~122533~~ 1,26,533 = 00


प्रतिवेदन

पथ का नाम :- सी० १ से मुर्तुजपुर
पथ की लं० :- १.५२१ KM.
प्राक्कलित राशि :- B. 127 533 = 2


माह जुलाई अगस्त में हुई अतिवृष्टि के फलस्वरूप विभिन्न नदियों एवं नालों में आये बाढ़ के चलते अधिकांश पथ क्षतिग्रस्त हो गये एवं यातायात बाधित हो गया।

जनता की परेशानी, एवं आने वाले आम चुनाव (बिहार विधान सभा) एवं विभागीय आदेश -मु० अ०-०४मु० विविध कार्य 23-40/2016-2729अनु० दिनांक-21.08.2020 के आलोक में क्षतिग्रस्त पथों के ईट टुकड़े एवं चिमनी छाई से भरकर यातायात पुर्नस्थापन किया गया। किये गये कार्य के अनुसार प्राक्कलन तैयार कर घटनोत्तर स्वीकृति हेतु समर्पित की जा रही है। कार्यहित में प्राक्कलन की स्वीकृति अपेक्षित है। ईट टुकड़ा की उपलब्धता कार्यस्थल से 8 कि०मी होने के कारण BRICK BATS के दर गणना में 8 कि०मी० लीड का प्रावधान किया गया।

प्राक्कलन को कार्य अंचल, दरभंगा द्वारा स्वीकृत अद्यतन दर के आधार पर तैयार कर अग्रेतर कार्यवाई हेतु समर्पित की जाती है।


कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा बेनीपुर,


सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल बेनीपुर,


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल बेनीपुर,

Flood Estimate
Name of Road:- T01 to Murtuzapur


Sl No	Particulars of Item	Quantity (In M ³)	Rate	Amount
1	E/W filling in Embankment & Flank in all kinds of Soil with 1000 m lead all complete job. As Per Specification & Direction of E/I	31.88	172.79	5509.00
2	Providing and laying Filling in ditches with brick bats including loading, unloading and light ramming all complete job. As per specification & Direction of E/I	42.75 45.38	1867.76	79847 84759.00
3	providing and laying NP3 Type RCC, HP .600 mm dia all completed job. As per specification & Direction of E/I	7.5	3000.00	22500.00


107856=00


S.F. - 31.88 x 34.81 x 10% = 111=0
42.75 x 1063 x 10% = 4544=0
4655=0

Add 12% GST =
1% L.C =
S.Fee. =

13532 12943=0
1128 1079=0
405 4655=0
126533=0
Total=


J.E.
RWD, Benipur


A.E.
RWD, Benipur


E.E.
RWD, Benipur

कार्यपालक अभियंता यादव कांकिण कार्य प्रगतिगत जमाना के प्रमाण 79847 (रुपये)
दिनांक 04/01/21 के द्वारा समर्पित जॉब प्रविष्टिगत के आधार पर
Post facto TA for Rs. 1,26,533=00 (Rupees one lakh twenty
Six thousand five hundred thirty three) only.

09.04.21

Superintending Engineer
R.W.D. (W) CIRCLE, DARBHANGA
09/04/2021

Flood Estimate


Name of Road:- T01 to Murtuzapur


Item No.1	Providing and laying Filling in ditches with brick bats including loading, unloading and light ramming all complete job. As per specification & Direction of E/I				
S.N	Chainage (In M)	Length (In M)	Average Width (In M)	Average Height (In M)	Qty
1	1400-1500 m	15.00	$(3.5+4.0)/2$	$(0.4+0.7)/2$	30.94
2	3700-3800 m	2.50	$(5+6)/2$	$(0.9+1.2)/2$	14.44
Total:-					45.38

Item No.2	E/W Filling in Embankment & Flank in all Kinds of Soil with 1000 m lead all complete Job. As Per Specification & Direction of E/I				
S.N	Chainage (In M)	Length (In M)	Average Width (In M)	Average Height (In M)	Qty
1	1400-1500 m	15.00	$(4+4.50)/2$	$(0.4+0.6)/2$	31.88
Total:-					31.88


Item No.3	Providing and laying NP3 Type RCC, HP.600 mm dia all complete job. As per specification & Direction of E/I		
S.N	Chainage (In M)	Length (In M)	Qty
1	3700-3800 m	2.5x3	7.50 m
Total:-			7.50 m


J.E.
RWD, Benipur


A.E.
RWD, Benipur


E.E.
RWD, Benipur

Physically verified and corrected as per site


A.E.

CB

219


Flood Estimate


Name of Road:- T01 to Murtuzapur

Item No.1	Providing and laying Filling in ditches with brick bats including loading, unloading and light ramming all complete job. As per specification & Direction of E/I				
S.N	Chainage (In M)	Length (In M)	Average Width (In M)	Average Height (In M)	Qty
1	1400-1500 m	15.00	$(3.5+4.0)/2$	$(0.4+0.7)/2$	30.94
2	3700-3800 m	2.50	$(5+6)/2$ 4.5	$(0.9+1.2)/2$	24.44 11.81
Total:-					45.38 42.75

Item No.2	E/W Filling in Embankment & Flank in all Kinds of Soil with 1000 m lead all complete Job. As Per Specification & Direction of E/I				
S.N	Chainage (In M)	Length (In M)	Average Width (In M)	Average Height (In M)	Qty
1	1400-1500 m	15.00	$(4+4.50)/2$	$(0.4+0.6)/2$	31.88
Total:-					31.88

Providing and laying NP3 Type RCC, HP.600 mm dia all complete job. As per specification & Direction of E/I			Total:- 7.50m
Item No.3			
S.N	Chainage (In M)	Length (In M)	Qty
1	3700-3800 m	2.5x3	7.50 m
Total:-			7.50 m


J.E.
RWD, Benipur


A.E.
RWD, Benipur


E.E.
RWD, Benipur