

GOVERNMENT OF BIHAR
FDR (2020-21)



बिहार सरकार

Name of Road:- Bhandar PWD Road to Padumker	Length-2.95 Km
Siswan	Block- Dhaka
Estimated Cost- Rs.:- 16,21,000.00	14,52,400.00

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- ~~भंडार पी. उन्नु. डी. रोड से पड़ुमुरे खीवान~~

प्रखंड का नाम :- दाका

पथ की लम्बाई :- 2.75 कि.मी.

शीर्ष :- 3054 F.D.R.

प्राक्कलित राशि :- र. 15,21,000/- 14,52,600/-

अनुसंधान अवधि :- निर्माणाधीन

~~भंडार पी. उन्नु. डी. रोड से पड़ुमुरे खीवान~~


प्रस्तुत प्राक्कलन ~~...~~ में अतिवृष्टि/बाढ़

से क्षतिग्रस्त पथाशों में यातायात पुनर्स्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि गो0...15,21,000/- रु0 है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से मरने का प्रावधान किया गया है।

प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


1.5.2020

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, दाका।


07/07/2020

सहाय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, दाका


07/07/2020


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, दाका

Estimate for Restoration work of Road from Bhandar PWD Road to Padumker Siswan
~~for the year 2020-21 in Dhaka Block.~~ for the year 2020-21 in Dhaka Block.

Length:- 2.95 Km

SL N.	Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
1	Labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bats)				
	CH:-350M to 400M				
	50.00x4.10x0.250 = 51.25M ³				
	CH:- 500M to 550M				
	50.00x4.10x0.300 = 61.50M ³				
	CH:-600M to 650M				
	50.00x4.10x0.300 = 61.50M ³				
	CH:-2150M to 2350M				
	200x4.10x0.400 = 328.00M ³				
	CH:-2450M to 2650M				
	200x4.10x0.350 = 287.00				
	Total = 789.25M ³	M ³	789.25	2053.84	16,20,993.00
			Total=	Rs.	16,20,993.00
				Say Rs.	16,21,000.00


 JE.


 AE.


 EE.

It is to be noted that is accorded for Rs. 14,52,600 = Fourteen Fifty Six hundred only.


 S.E. (R.W.D.)
 works Circle
 Motihari
 29-12-20

Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Bhandar PWD Road to Padumker Sawa

(A) For Road

1. Damage Location Chainage:-
2. Damage Length:- 550 M
3. Name of Damage:- Road damaged due to Flood.
4. Details of Restoration Work:-
 - (i) Material being used in Restoration works:- Brick ball
 - (ii) Equipments Tools being used in restoration works:-
 - (iii) Procedure take up in restoration works:- Departmental
 - (iv) Restored Length:- 550 M.


24/12/2018
Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul