

RURAL WORKS DEPARTMENT GOVT. OF BIHAR



Name of Work:-Simauli to Waterwage Bhand.

Block:- Pupri.

F.D.R

Rs. ~~174231.00~~

167476.00

Year-2020-21

Name of Circle:- R.W.D, Works Circle, Sitamari.

Name of Division:- R.W.D., (W) Division, Pupri.

District:-Sitamarhi

~~174231.00~~

~~05/11/2020~~

21/12/20

06.06.13

[illegible]

16/06/21

Handwritten signature: *[Signature]*
Date: 30.12.2020
Place: RWP, Belgaum

~~Technically approved for Rs. 1,74,231=00 (Rupee One lakh
Seventy four thousand two hundred thirty one) only.~~

Self 12/5/21

Schedule of Quantity

Name of Road:- Simaulli to Waterwage Bhand.

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	401.00	0.00
2	Providing and laying of Brick Bat obtained from Chimney with machanical means with all spreading, grading to required slope and compacted at OMC to achieve required density with all complete as per the direction of engineer in charge.	111.3104			0.00
	Less 20% for Voids	22.26207			
		89.0483	Cum	1546.00	137668.641
3	Single bamboo paiaiding/ walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and Struts 1.5m apart longitudinally and providing brush wood as per drawing and technical specification clause 1302.5	0.00	m	172.62	0.00
4	Providing, Laying and placing empty cement bag filled with local sand including stitching with sutall etc. do.....do.....all complete job as per specification and direction of E/L. (including Royalty and all Taxes)	0.00	no.	23.12	0.00
5	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row with old available pipe	0.00	m	3158.69	0.00
6	Providing Quarry Material Rabbish for filling the voids in bricks batsdo.....all complete job as per specification and direction of E/L.	21.3989			
	Taking 20% of Brick Qty for Rabbish	22.26207	Cum	742.00	16518.4559
					15877.9838
	Total				154187.097
	Say				154187.00
	Total				148908.7814
					148909.10

21/12/20

21/12/20

21/12/20

Details of Measur of ditches filled by brick bats and rabbish

Name of Road:- Simaull to Waterwage Bhand.

L	W	H	VOLUME
9.50	3.750	2.40	85.5000
6.00	2.950	2.40	42.4800
4.50	3.100	2.25	31.3875
16.50	2.750	2.10	95.2875
5.30	2.400	0.41	5.1516
5.00	2.250	0.45	5.0625
		A	264.8691
9.50	2.900	1.43	39.2588
6.00	2.500	1.50	22.5000
4.50	2.600	1.50	17.5500
16.50	2.400	1.88	74.2500
		B	153.5588
Total (in Cum)			111.3104
0	0		0.00
Cement Bage			

[Signature]
21/12/20

[Signature]
21/12/20

[Signature]
21/12/20

[Signature]
28/12/20
A.E.
RWD Bhand

111.3104

264.8691

5.1516

85.5000

UT DATA

STRIC

LABITATION CODE

BLOCK

ROAD DETAILS

From (Chainage)

To (Chainage)

Flush Drain (Cum)

Road Connecting To

Brick Soling for Dismantling

CC Road for Dismantling

BT Road for Dismantling

Format 2 B : CD's

CD Details

Name of the Road

Existing CD:

Flush Causeway

HP Culvert 1 Row

HP Culvert 2 Row

HP Culvert 3 Row

HP Culvert 4 Row

0.5m Span Slab Culvert

1.0m Span Slab Culvert

1.50m Span Slab Culvert

2m Span Culvert

3m Span Culvert

4m Span Culvert

5m Span Culvert

6m Span Culvert

2x6m Span Slab Culvert

Vented Causeway

Below 600mm Dia Culvert

Bridge

Prepared By

Sitamathi

Pupri

Name of Road:- Simaulli to Waterwage Bhand.

0.00km

0.01km

4.0 km

Name of Road:- Simaulli to Waterwage Bhand.

Nos

Works Division, Pupri.