

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधुबनी।

पत्रक - 1259313

दिनांक : 25.05.2021

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मधुबनी

अभियंता अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मधुबनी

विषय:- ग्रामीण कार्य विभाग, कार्य प्रमंडल, दर्जा-2 के अधीन रिकमांडा एव मनीगाछी प्रखंड में वर्ष 2020 में बाट/अविवृष्टि से क्षतिग्रस्त 101 जमी/पुलों में कारगरे मदे पुनरुद्धारण कार्य से संबंधित पथों का प्राकलन के समय में।

प्रमाण:- मजदी का पत्रक-871 अगुठ दिनांक-10.04.2021

महाराज, उपरोक्त विषयक प्रासंगिक पत्र से प्राप्त यातायात पुनरुद्धारण के निम्नांकित प्राकलन को गठित

जीव वल द्वारा जीवोपरान्त आवश्यक कार्रवाई हेतु समितित की जाती है। विवरणी निम्न प्रकार है:-

Sl No	Block	Name of Road	Length (KM)	Qty. (Brick Bats) (M3)	Remarks
1	Manegachhi	Ashok Paper Mill Chakkai to Bideswar Sthan road	9.150	650.160	
2	Manegachhi	PMGSY Path Vihari to S.H. 67 Bhatpara road	1.970	315.940	
3	Manegachhi	PMGSY Road Vihari to Mithanadi talu	0.530	351.710	
4	Manegachhi	T04 to Bhatra	1.170	257.390	
5	Manegachhi	Lahori State Boring to Indrathi H.O. Road tak	1.215	277.840	
6	Manegachhi	PWD Path to Kivadi talu	1.100	168.340	
7	Manegachhi	PMGSY road to Kivadi talu Bhatpara	1.600	73.760	
8	Manegachhi	PWD Patna Baharwa to Karampur Bhatpara via Vadi talu	3.240	694.930	
9	Manegachhi	Luhana R.V. Station to Sonpur via road	1.500	171.080	
10	Manegachhi	PWD Path Katma Baharwa to Bhatpara	1.600	250.920	
11	Manegachhi	Bhatpara Jagadishpur to Modin talu Jagadishpur	0.770	85.490	
12	Manegachhi	T02 to Bhatra	1.027	103.020	
13	Manegachhi	PWD road Bhatra to PWD road Karampur	1.590	519.680	
14	Manegachhi	PMGSY Bhatra to Panchanabi	1.650	226.500	
15	Manegachhi	R.O. road to Bhatpara talu	1.170	444.500	
16	Manegachhi	Upin Majal chok to Amritnagar road	3.800	289.330	
17	Manegachhi	PMGSY Path to Larkur Mahadali talu road	1.330	88.230	
18	Manegachhi	PMGSY road Sakhi to Khampani Secma	0.500	237.750	
19	Manegachhi	PWD road Bhatpara to Kanakpur	1.030	138.520	
20	Manegachhi	PWD Sasvadi Daxi ghari to Danji Masul talu via Refaral Hospital tak	1.500	638.430	
21	Manegachhi	T04 Brahmapara to Sakhi talu road	2.440	243.010	
22	Manegachhi	PMGSY Path to Larkur Brahmapara talu	1.050	429.000	
23	Manegachhi	Sahant talu to School	2.500	559.620	
24	Manegachhi	R.O. road to Karampur Modin talu Bhatpara	1.090	679.100	
25	Manegachhi	Makhi ghari to Bideswar Bhatpara via Athan	3.200	472.180	
26	Manegachhi	PMGSY Sadak to Pawan talu	1.000	286.170	
27	Manegachhi	Pradip Vadi talu to Mushari H.O. via Vadi talu School tak	2.000	481.430	
28	Manegachhi	Manna Bahara Pawan talu to Makhi talu	1.110	341.800	

Name of Road:-	PWD Suvidha Das ke Ghar to Dan ji Mandal Tola Vai Refaral
Manicock:-	

District:-	Darbhanga
------------	-----------

SUB HEAD : BRICK BATS

Laying & Distribution of Brick bats on affected Road portion as per specification to meet the required slope and proper light Ramming from a specified lead as per direction of E/I.

SI No	Chainage (in M)		Nos.	Length (m)	Width (Avg.) (m)	Height/Thickness (Avg.) (m)	Quantity	Rate (In Rs.)	Amount (In Rs.)
	From	To							
	0	18	1	27.00	$\frac{3.5+4.5}{2}$ $\frac{4.50+6.50}{2}$	$\frac{0.7+0.9}{2}$ $\frac{1.00+1.80}{2}$	$\frac{87.40}{207.90}$	1867.76	388307.00
		300	1	16.00	$\frac{3.5}{2}$ $\frac{4.50+6.50}{2}$	$\frac{0.60}{2}$ $\frac{0.90+1.60}{2}$	$\frac{48.00}{110.00}$	1867.76	205454.00
		400	1	21.00	$\frac{3.5}{2}$ $\frac{4.50+6.50}{2}$	$\frac{0.75+1.25}{2}$ $\frac{0.75+1.25}{2}$	$\frac{56.28}{115.50}$	1867.76	215726.00
		650	1	30.00	$\frac{3.5}{2}$ $\frac{4.50+6.50}{2}$	$\frac{0.75+1.20}{2}$	$\frac{117.00}{160.88}$	1867.76	300473.00
			1	70.00	$\frac{3.5}{2}$ $\frac{3.00+5.00}{2}$	$\frac{1.20+1.50}{2}$ $\frac{1.20+1.50}{2}$	$\frac{330.75}{462.00}$	1867.76	862905.00
			Total=	164.00		$\frac{638.43M^3}{1056.28}$	$\frac{2}{1867.76}$		1972865.00 11,92
									236744.80 Rs. 14
									19729.00 - Rs. 119
									11222.00 - Rs. 67
									2341620.00
									2341620.00

[638.43M³ X 1063 X 10%.] Add SF @ 10% On Material Cost

Total Amount in Rs. =

Total Say Amount in Rs. =

Total K₂O 14,15,315 = 0

Assistant Engineer

Executive Engineer

RWD (W) Division, Darbhanga-2

RWD (W) Division, Darbhanga-2

RWD (W) Division, Darbhanga-2

Checked by

12/11/21

۱۷۷

76-