

FDR

DISTRICT :- DARBHANGA


BLOCK :- BAHERI


Name of Raad :- Motarable Work for Gewal Chowk to Bhaghaul in Hayaghat Vidhan Sabha


Length of the Road:- 0.540 KM
Effective Length 0.116 KM.

GENERAL ABSTRACT OF COST

SI No.	Item of Work	Amount (in Rs.)
1	Cost for restoration	80,586.37
2	Add 12 % GST	9,670.36
3	Add Seigniorage	4,586.42
4	Add 1 % Labour Cess	805.86
Total cost:-		95,649.02



14.12.2020
Junior Engineer
Baheri


15/12/20
Assistant Engineer
Baheri


Executive Engineer
R.W.D.(W) Division, Darbhanga-1

नार्थपालक अमिषता, मा. का. वि. नार्थप्रमंडल पुलपराल को फा. का. :- 542 अ. 30
दिनांक: 07/04/2021 के ब. का. समिति बा. प्रवि. के अ. शा. ल.


Post-facto T/A for Rs 95649=00 (Rupees Ninety five thousand six hundred forty nine) only



09.04.21
Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2021


Detailed estimate for making moterable road.

Name of Raad :- Motarable Work for Gewal Chowk to Bhaghaul in Hayaghat Vidhan Sabha
 DCK :- BAHERI
 TRICT :- DARBHANGA
 V.D. Works Division Darbhanga-1

No.	Item	Unit	No.	Length (m)	Breadth (m)	Depth / Height (m)	Quantity	Rate	Amount
1	Labour and placing of brick bats with light raming including cost of brick bats by tractor	cum	From Booth 160						
			0.000 KM to 1.000 KM						
			1	10.00	2.00	0.250	5.000	✓	
			1	16.00	1.80	0.200	5.760	✓	
			1	8.00	1.75	0.250	3.500	✓	
			1	10.00	2.60	0.250	6.500	✓	
			2	5.00	1.80	0.180	3.240	✓	
			1	2.00	1.30	0.200	0.520	✓	
			1	4.00	1.40	0.200	1.120	✓	
			2	5.00	1.75	0.220	3.850	✓	
			1	3.00	1.60	0.200	0.960	✓	
			2	4.60	2.30	0.600	12.696	✓	
						Total	43.146	1867.76	80586.4
									80586.4


 11/12/2020
 Junior Engineer
 Baheri


 15/12/20
 Assistant Engineer
 Baheri


 15/12/20
 Executive Engineer
 R.W.D.(W) Division, Darbhanga-1