



ग्रामीण कार्य विभाग

पथ का नाम :- जारदो के स्कराम
कार्य प्रमण्डल :- बेनीपुर।
कार्य अंचल :- दरभंगा।
प्रखण्ड का नाम :- बेनीपुर।
प्राक्कलित राशि :- Rs. ~~48796.00~~ 51,255.00


प्रतिवेदन


पथ का नाम :- सारखी ले स्कराम
पथ की लं० :- ०.८५२ Km
प्राक्कलित राशि :- Rs. ५८७९६००


माह जुलाई अगस्त में हुई अतिवृष्टि के फलस्वरूप विभिन्न नदियों एवं नालों में आये बाढ़ के चलते अधिकांश पथ क्षतिग्रस्त हो गये एवं यातायात बाधित हो गया।

जनता की परेशानी, एवं आने वाले आम चुनाव (बिहार विधान सभा) एवं विभागीय आदेश -मु० अ०-०४मु० विविध कार्य २३-४०/२०१६-२७२९अनु० दिनांक-२१.०८.२०२० के आलोक में क्षतिग्रस्त पथों के ईट टुकड़े एवं चिमनी छाई से भरकर यातायात पुर्नस्थापन किया गया। किये गये कार्य के अनुसार प्राक्कलन तैयार कर घटनोत्तर स्वीकृति हेतु समर्पित की जा रही है। कार्यहित में प्राक्कलन की स्वीकृति अपेक्षित है। ईट टुकड़ा की उपलब्धता कार्यस्थल से ८ कि०मी होने के कारण BRICK BATS के दर गणना में ८ कि०मी० लीड का प्रावधान किया गया।

प्राक्कलन को कार्य अंचल, दरभंगा द्वारा स्वीकृत अद्यतन दर के आधार पर तैयार कर अग्रेतर कार्यवाई हेतु समर्पित की जाती है।


कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा बेनीपुर,


सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल बेनीपुर,


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल बेनीपुर,

Flood Estimate
Name of Road:- Jarso to Dakaram

Sl No	Particulars of Item	Quantity (In M ³)	Rate	Amount
1	Providing and laying Filling in ditches with brick bats including loading, unloading and light ramming all complete job. As per specification & Direction of E/I	23.12	1867.76	43182.6112

R. 43183=00


SF. $23.12 \times 1867.76 \times 107 = 2457.65$


Add 12% GST
1% L.C


	5182
	432
	48796
Total=	R. 2458=00

SF

R. 51255=00


J.E.
RWD, Benipur


A.E.
RWD, Benipur


E.E.
RWD, Benipur

कार्यपालक अभियंता शारदापुरी की याज्ञिक जायन्तार के फास 798 (अ.क.)
दिनांक 9/4/2021 के द्वारा समिति गौर प्रविष्टि के मादाल 48

Post facto T.A for R. 51255=00 (Rupees fifty one thousand
two hundred fifty five) only.

09.04.21

Superintendent Engineer
R.W.D. (W) CIRCLE, DARBHANGA
09/04/2021

Flood Estimate

Name of Road:- Jarso to Dakaram

Item No.1	Providing and laying Filling in ditches with brick bats including loading, unloading and light ramming all complete job. As per specification & Direction of E/I				
S.N	Chainage	Length (In M)	Average Width (In M)	Average Height (In M)	Qty
1	Ch 315-330 m	8.00	$(4+4.5)/2$	$(0.3+0.85)/2$	19.55
2		3.00	1.50	0.20	0.90
3	360 m	2.75	1.70	$(0.2+0.3)/2$	1.17
4		3.00	2.00	$(0.2+0.3)/2$	1.50
Total=					23.12

[Signature]
J.E
RWD, Benipur

[Signature]
21/12/2020
A.E
RWD, Benipur

[Signature]
E.E
RWD, Benipur

physically verified and corrected on the site

[Signature]
07.04.21
A.E

[Signature]
21/4
E.E

Flood Estimate

Name of Road:- Jarso to Dakaram

Item No.1	Providing and laying Filling in ditches with brick bats including loading, unloading and light ramming all complete job. As per specification & Direction of E/I				
S.N	Chainage	Length (In M)	Average Width (In M)	Average Height (In M)	Qty
1	Ch 315-330 m	8.00	$(4+4.5)/2$	$(0.3+0.85)/2$	19.55
2		3.00	1.50	0.20	0.90
3	360 m	2.75	1.70	$(0.2+0.3)/2$	1.17
4		3.00	2.00	$(0.2+0.3)/2$	1.50
Total=					23.12

[Signature]
J.E
RWD, Benipur

[Signature]
21/12/2020
A.E
RWD, Benipur

[Signature]
E.E
RWD, Benipur



2/11/2020

जिला व संग्राम



Latitude: 26.050345
Longitude: 86.119234
Accuracy: 2605.0 m
Time: 12-09-2020 11:01
Note: Jaiso to Dabhi

81
2/12/2020