

Detailed Estimate of Flood Damaged Road

Name of Division:-
Name of Work:-
Name of Scheme:-
Length(in Km):-

Darbhanga-2
Ahiyari Dakshini REO Road se Link Road Uttam ke Chai dukan se Gualb yadav ke Ghar tak
FDR 2020
1.8 km

Block:- Jale
District:- Darbhanga

Sl. No.	SOR Sl.No.	Items of Work
1	6.61 WRD BIHAR	Providing and laying of Bricks bats with carriage by tractor loading with front end loader with light ramming etc all complete job

Particulars	Details of Actual Measurement				Quantity(m ³)
	No.	Length(m)	Breadth(average)(m)	Depth(average)(m)	
Chainage 0-290m	1	9.00	2.44	0.25+1.00+0.30/3	21.946
Chainage 0-290m	1	15.00	3.05	0.20+0.76+0.15/3	34.839
Chainage 0-290m	1	16.00	3.05	0.61+0.15	29.729
Chainage 320-410m	1	10.00	3.05	0.76+0.20	23.226
Chainage 320-410m	1	12.00	3.05	0.61+0.15	22.297
Chainage 320-410m	1	10.00	2.74	0.76+0.20	20.903
Chainage 320-410m	1	12.00	2.74	0.61+0.15	20.067
Chainage 320-410m	1	13.00	2.74	0.61+0.15	21.739
Chainage 320-410m	1	17.00	2.74	0.76+0.30	35.535
Chainage 440-910m	1	14.00	2.74	0.61+0.15	23.412
Chainage 440-910m	1	13.00	3.05	0.76+0.20	30.193
Chainage 440-910m	1	10.00	2.74	0.61+0.15	16.723
Chainage 440-910m	1	11.00	2.74	0.20+0.76+0.15/3	22.994
Total					323.602

Post-Feet T/A for Rs 2,40,829 = 10
(Charges Two lacs forty thousand eight hundred and twenty nine) only

Superintending Engineer
RWD, Works Circle, Darbhanga

Junior Engineer
15.1.2021

Asstt Engineer
28/1/2021

Executive Engineer
28/1/2021

108.635 m³
1867.76/m³ = 202904 = 10
24,348 = 10
2,029 = 10
11,548 = 10
Total Rs 2,40,829 = 10