



FLOOD DAMAGE REPAIR (FDR)

YEAR 2020-21

FOR T/A

DISTRICT :- **BEGUSARAI**
BLOCK :- **BHAGWANPUR**

CONSTRUCTION COST	:-	Rs. 6.409 Lac
TOTAL COST	:-	Rs. 6.409 Lac

GTSNY YOJNA

NAME OF ROAD :- **FLOOD DAMAGE REPAIR OF BASAHI TO CHURAMANCHAK**

TOTAL LENGTH	:	1.800 KM
LENGTH DAMAGE DUE TO FLOOD	:	0.252 KM.

SUBMITTED BY:
EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION, TEGHRA

Name of Road :- Flood Damage Repair of Basahi to Churamanchak

Year 2020-21

District :-

Block :-

Begusarai

Bhagwanpur

GENERAL ABSTRACT OF COST

Sl No.

Item of Work

Amount (in Rs.)
As Per Estimate

1
2
3

COST OF FDR

5,51,214.00

Add L.C. @1%

5,512.00

ADD GST @ 12%

66,146.00

Sub Total Rs. :-

6,22,872.00

Add S.F. @ 10% on Material Rate

17,932.00

Total Rs. :-

6,40,804.00

Say Rs. :-

6,40,900.00

[Signature]
19/10/2020

J.E

RWD Teghra

[Signature]
19/10/20

A.E

RWD Teghra

[Signature]
19.10.2020

E.E.

RWD Teghra

Total Amount Approved for Rs 6,40,900 = 64 Lakhs fourty thousand nine hundred only.

[Signature]
17.2.2021
बसोबस बापलगा.
बापलगा बापलगा विभाग
बापलगा बापलगा, बापलगा
B/M

SDB SL. NO	MOR D Ref. N	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (In Rs.)
1		Supplying of empty cement bag (sythetic should be old but in good condition of 1.2 calcapacing) with carriage,labour cost of roll nylon for streching of empty bag through local sand,laying,stacking properly.....all complete job as per specifications and								
		Qty From Calculation	Nos	540.54 X	25.00			13,514.00	29.15	3,93,964.00
		Sheets								

Providing brick bats including ,spreading,laying, hand packing with CI hammers in layers has exceeding 75mm thick including cost of light barriers,danger equal,choukidar,taxes,royalty etc all complete job, as per specifications and direction of E/I including cost of bricks,.....all complete job

Qty From Calculation	93.6	1.680 02	1,57,250.00
Sheets			

Total = 551214.00

6/12/19
19/10/2020

J.E

RWD Teghra

6/12/19
19/10/2020

A.E

RWD Teghra

6/12/19
19/10/2020

E.E.

RWD Teghra

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमण्डल, मंझौल-बखरी।

पत्रांक-...17.5420/मंझौल-बखरी,

दिनांक-...11/02/21...

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, मंझौल-बखरी।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, तेघड़ा।

विषय : शीर्ष-FDR अन्तर्गत पथों की जाँच प्रतिवेदन समर्पित करने के संबंध में।

प्रसंग : आपका पत्रांक-201375 दिनांक-09.02.2021

महाशय,

उपर्युक्त विषयक प्रसांगिक पत्र के संबंध में कहना है कि ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेघड़ा के अधीन शीर्ष-FDR अन्तर्गत वर्ष-2020-21 के पथों की जाँच कर जाँच प्रतिवेदन समर्पित की जाती है।
अनु०-प्रतिवेदन संलग्न।

विश्वासभाजन


11/02/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग, कार्य प्रमण्डल,
मंझौल-बखरी।

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तैयडा द्वारा करार गए पथों की जाँच से संबंधित प्रतिवेदन

क्र.	पथ का नाम	क्षेत्रफल म० (फी० #)	करार गए कार्य	करार गए निर्माण कार्य की राशि (रु० #)	GST @ 12%	L. Cess @ 1%	S. Fee @ 10%	Total	अवधि
1	Flood Repair of Nurpur Bhagwati Asthan To Nurpur.	261	Sand Bag	416539.00	49985.00	4165.00	6045.00	478734.00	कार्य पूर्ण।
2	Flood Damage Repair of Road Chamtha REO Goptol To Cheriyatok.	10	Bricks Bats, Sand Bag	117758.00	14131.00	1178.00	7685.00	140752.00	कार्य पूर्ण।
3	Flood Damage Repair of Barauni PWD Road To Alapur Pasopur.	22	Sand Bag, E/w, Bricks Bats, GSB	122153.00	1222.00	14658.00	6827.00	144860.00	कार्य पूर्ण।
4	PMGSY Dasaratpur Road House of Ganga Giri To MMGSY Satbhaiya Tola.	20	E/w, Bricks Bats, GSB & Sand Bag.	53092.00	6371.00	531.00	1944.00	61938.00	कार्य पूर्ण।
5	Flood Damage Repair of Road NH Ihamatia Gat To Gopalpur.	163	Bricks Bats, Sand Bag, GSB	579759.00	69571.00	5798.00	21492.00	676620.00	कार्य पूर्ण।
6	Flood Damage Repair of REO Road Maranchikala To Harijan Tola Bhawanipur Ghat.	73	Bricks Bats, Sand Bag.	870266.00	104432.00	8703.00	23269.00	1011670.00	कार्य पूर्ण।
7	Flood Damage Repair of Basahi To Churamanchak.	252	Sand Bag, Brick bats	551214.00	66146.00	5512.00	17932.00	640804.00	कार्य पूर्ण।
8	Flood Repair of Patni Chowk RWD Road To Makratol.	181	Sand Bag.	235259.00	28231.00	2353.00	4544.00	270387.00	कार्य पूर्ण।
9	Flood Repair of X-Road Chan Barkhut Chamtha Ghat.	360	Sand Bag, E/w	310101.00	37212.00	3101.00	6015.00	356429.00	कार्य पूर्ण।
10	Flood Damage Repair of Kadramab (PWD Road) To (Dharampur) Bachhawara.	193	Sand Bag, GSB	183943.00	22073.00	1839.00	4545.00	212400.00	कार्य पूर्ण।
11	Flood Damage Repair of Ganpataul To Gauspur Sohilwara.	139	E/w, Bricks Bats, Sand Bag.	371602.00	44592.00	3716.00	16593.00	436503.00	कार्य पूर्ण।

उपरोक्त सभी पथों की जाँच की गई जो संतोषप्रद है।

(Signature)
11/07/2021

Executive Engineer
RWD (W) Div., Manjhaoul-Bakhari