



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

Head- FDR(2245)

YEAR 2020-21

Name of Division - R.W.D. (W) Division Dhaka

Block :- Ghorasahan

District :- East Champaran

Name of Road - Estimate for Emergent Repair of Road breaches (Damaged by Flood) for Purnahiya Vijayi Road to Purnahiya Pararia Rajput Tola Ward No-01

Length -

K.M

ESTIMATED COST :- 790100.00 Lakh

SUBMITTED BY:

**EXECUTIVE ENGINEER,
RWD WORKS DIVISION, DHAKA**

तकनिकी प्रतिवेदन

पथ का नाम :- पुर्नस्थापन विभाग की ओर से पुर्नस्थापन परीक्षा 21.06.20 के लिए राशि :- 1

प्रखंड का नाम :- बरगुहा

शीर्ष :- 111637

प्राक्कलित राशि :- ₹ 790100.00

अनुसूचण अवधि :- 21.06.20

प्रस्तुत प्राक्कलन पुर्नस्थापन विभाग की ओर से पुर्नस्थापन परीक्षा 21.06.20 के लिए राशि में अतिवृष्टि / बाढ़ से क्षतिग्रस्त पथांशों यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि ... 790100.00 ₹0 है। प्रस्तुत प्राक्कलन सचिव, ग्रामीण कार्य विभाग, पटना के पत्रांक-2254 दिनांक-30.06.2020 के निर्देशानुसार तैयार किया गया है पथ में अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथांशों में ... Block ... से भरने का प्रावधान किया गया है।

प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।

23/12/2020

कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा बरगुहा

23/12/2020

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमंडल बरगुहा

23/12/2020

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बरगुहा

Name of Work:- Estimate for Emergent Repair of Road breaches (Damaged by Flood) for Purnahiya Vijayi Road to Purnahiya Pararia Rajput Tola Ward No-01

Head - 2245

Length-

Sl No.	Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Labour for laying dry graded Jhama Khoa or stone filter under Brick Pitching or Boulder Pitching in slope or apron including light ramming etc. all complete as per approved design, specification and direction of E/I.	cum	As Per	Appendix I			367.9 325.52	2147.41	790032.14 699,025.00
2		Providing and Laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, Protection Works, backfilling, concrete and masonry	M	0	2.50M	0	0	0	4744.43	0.00
3		Sand filling with Approved Materials seposited at site from roadway cutting and excavation from drain and foundation of other strecture graded and compected as per Technical Specification	M3					0	400.59	0.00
TOTAL (in Re.)										790032.14
Say Total Rs-										790100.00 6,99,000.00

gypel
23/12/2020
Junior Engineer,
Rural Works Department,
Works Section, Dhaka
Ghorasien

gypel
23/12/2020
Assistant Engineer,
Rural Works Department,
Works Sub Division, Dhaka
Ghorasien

JEP
23/12/2020
Executive Engineer,
Rural Works Department,
Works Division, Dhaka

~~Post Facto T.A./TS is accorded for Rs. 7,90,000.00 = ~
(.....crore Seven lacs Ninety thousand
.....hundred) only.~~

S.E. (R.W.D.)
works Circie
Motihari

Post fact, J.A. is accorded for Rs. 6,99,000.00
(.....) crore SIX lacs ninety nine
..... hundred

8/4/2021

S.E. (RWD)
works Circle
Muzhianj

19-03-21

Name of Work:-

Estimate for Emergent Repair of Road breaches (Damaged by Flood) for Purnahiya
Vijayi Road to Purnahiya Pararia Rajput Tola Ward No-01

Appendix - I

Measurement for surfacing the Breach with Brick Bats

Sl. No.	Chainage Km	Length (M)	Avg. Width In Meter	Avg. Depth In Meter	Quantity (Cum)
1	0.700	4.000	1.600	0.400	2.560
2	0.750	15.000	$\frac{7.10+4.20}{2}$	$\frac{3.000}{2.5}$	$\frac{254.250}{211.87}$
3	0.800	5.000	$\frac{3.00+2.10}{2}$	1.400	17.850
4	0.880	12.000	$\frac{4.00+2.30}{2}$	2.200	83.160
5	0.980	6.000	2.100	0.800	10.080
Total					367.900

325.52

[Signature]
23/12/2020
Junior Engineer
Rural Works Department,
Works Section, Dhaka
Ghanshu

[Signature]
23/12/2020
Assistant Engineer
Rural Works Department,
Works Sub Division, Dhaka
Ghanshu

[Signature]
23/12/2020
Executive Engineer,
Rural Works Department,
Works Division, Dhaka

Inspection Report for Flood Damage Works

Date :-

1 Name of PIUs - Executive Engineer, RWD, Dhokas

2 Name of Block - Ghorsehan

Name of Road - Punshiga Vijayi Road to Punshiga Bards Rajput
Tola ward NO - 01

(A) For Road

1 Damage Location/Chainage :-

2 Damage Length :-

3 Nature of Damage:- Water logging

4 Details of Restoration Works:-

(i) Material being used in Restoration works:- Bricks Bats

(ii) Equipments/ Tools being used in Restoration works:-

(iii) Procedure taken up in Restoration works:- Departmental

(iv) Restored Length: 42M

Signature of Inspecting officer
(Executive Engineer)

R.W.D, W.D.

28/12/2020
Scanned by CamScanner