

Inspection Report for Flood Damage Works

Date

1. Name of PIU - Executive Engineer, RWD, Dhaka

2. Name of Block - Bankatwa

3. Name of Road - REO road Nimuysa Dhumnagar to Pokhalisa
(A) For Road

4. Damage Location/Chainage :-

5. Damage Length :- 111.0m

6. Nature of Damage:- Water logging.

7. Details of Restoration Works:-

(a) Material being used in Restoration works:- Brick bats

(b) Equipments/ Tools being used in Restoration works:-

(c) Procedure taken up in Restoration works:- Departmental

(d) Restored Length 111.0m

Signature of Inspecting officer:
(Executive Engineer)

R.W.D, W.D.

Scanned by CamScanner



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

Head- FDR(2245)

YEAR 2020-21

Name of Division - R.W.D. (W) Division Dhaka
Block :- Bankatwa
District :- East Champaran

Name of Road - Estimate for Emergent Repair of Road breaches (Damaged by Flood) for REO Road Nimuiya Dhumnagar to Pokhariya
--

Length - 2.169 K.M								
ESTIMATED COST :- 85400.00 Lakh								

SUBMITTED BY:

EXECUTIVE ENGINEER,
RWD WORKS DIVISION, DHAKA

तकनीकी प्रतिवेदन

पथ का नाम :- R.E.O रोड निमुइया खुमनगर से पोरवारिया (2.169 Km)

प्रखंड का नाम :- पनकटवा

शीर्ष :- PMGSY

प्राक्कलित राशि :- 85,400 = 00


अनुरक्षण अवधि :- निर्माणाधीन

प्रस्तुत प्राक्कलन R.E.O रोड निमुइया खुमनगर से पोरवारिया में अतिवृष्टि / बाढ़ से क्षतिग्रस्त पथांशों यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि ... 85,400 = 00 है। प्रस्तुत प्राक्कलन सचिव, ग्रामीण कार्य विभाग, पटना के पत्रांक-2254 दिनांक-30.06.2020 के निर्देशानुसार तैयार किया गया है पथ में अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथांशों में Brick bats से भरने का प्रावधान किया गया है।

प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


23/12/2020
कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा पनकटवा


23/12/2020
सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमंडल पनकटवा


23/12/2020
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, टाका

Name of Work:- Estimate for Emergent Repair of Road breaches (Damaged by Flood) for REO Road Nimuiya Dhumnagar to Pokhariya

Head - 2245 Length- 2.169 km

Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
1	Labour for laying dry graded Jhama Khola or stone filter under Brick Pitching or Boulder Pitching in slope or apron including light ramming etc. all complete as per approved design, specification and direction of E.I.	cum	As Per	Appendix I			39.765 37.165	2147.41	85391.76 79,808 = w
2	Providing and Laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, Protection Works, backfilling, concrete and masonry	M	0	2.50M	0	0	0	4744.43	0.00
3	Sand filling with Approved Materials seposited at site from roadway cutting and excavation from drain and foundation of other structure graded and compacted as per Technical Specification	M3					0	400.59	0.00
TOTAL (in Re.)									85391.76
Say Total Rs-									85400.00 79,800 = w

[Signature]
23/12/2020
Junior Engineer,
Rural Works Department,
Works Section, Bankatwa

[Signature]
23/12/2020
Assistant Engineer,
Rural Works Department,
Works Sub Division, Bankatwa

[Signature]
23/12/2020
Executive Engineer,
Rural Works Department,
Works Division, Phaka

For Facts T.A.T.S is accorded for Rs. 79,800 = w
(.....) crore.....lacs.....thousand
Eight hundred.....) only.

[Signature]
12/5/21
S.E. (R.W.D.)
works Circle
Motihari
29-4-21

Name of Work:-

Estimate for Emergent Repair of Road breaches (Damaged by Flood) for REO Road
Nimuiya Dhumnagar to Pokhariya

Appendix - I

Measurement for surfacing the Breach with Brick Bats

Sl. No.	Chainage	Length (M)	Avg. Width In Meter	Avg. Depth In Meter	Quantity (Cum)
1	0.180	45.000	3.30	0.150	22.275
2	0.230	10.000	1.500	0.150	2.250
3	0.295	2x18	1.120	0.200 0.15	8.640 6.04
4	0.430	2x20	1.100	0.150	6.600
Total					39.765 37.165

[Signature]
23/12/2020
Junior Engineer
Rural Works Department,
Works Section, ...*Bankatwa*

[Signature]
23/12/2020
Asistant Engineer
Rural Works Department,
Works Sub Division, ...*Bankatwa*

[Signature]
23/12/2020
Executive Engineer,
Rural Works Department,
Works Division, ...*Dhaka*