



Rural Works Department, Govt of Bihar

Head- FDR(2245)

YEAR - 2020 - 21

Name of Division - R.W.D. (W) Division

Block :- Ghorasahan

District :- East Champaran

Name of Road - Estimate for Emergent Repair of Road breaches (Damaged by Flood) for Ghorasahan Bakulia path to Bakulia ward No -06 (Saw Tola)

Length -

ESTIMATED COST :- 491500.00

SUBMITTED BY:

EXECUTIVE ENGINEER,
RWD WORKS DIVISION,

तकनीकी प्रतिवेदन

पथ का नाम :- पोडाहटन बुल्डीया रोड से बुल्डीया कार्ड नं० - 06 (साव रोला)

प्रकलन का नाम :- पोडाहटन

शीर्ष :- NM45Y.

प्राक्कलित राशि :- 4,91,500/-

अनुरक्षण अवधि :-

प्रस्तुत प्राक्कलन पोडाहटन बुल्डीया रोड से बुल्डीया कार्ड नं० - 06 (साव रोला) में अतिवृष्टि बाढ़ से क्षतिग्रस्त पथांशों यातायात पुनर्स्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि ... 4,91,500/- रूपी है। प्रस्तुत प्राक्कलन सचिव, ग्रामीण कार्य विभाग, पटना के पत्रांक-2254 दिनांक-30.06.2020 के निर्देशानुसार तैयार किया गया है पथ में अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथांशों में Block Boli से भरने का प्रावधान किया गया

प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।

12/12/2020
J.E.

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा पोडाहटन

22/12/2020
J.E.

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमंडल पोडाहटन

23/12/2020
J.E.

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, 2/12/20

Veri...
J.E.

22/12/2020
E.E. P.W.D
Ra Xau

of Work:- Estimate for Emergent Repair of Road breaches (Damaged by Flood) for

Ghorasahan Bakulia path to Bakulia ward No -06 (Saw Tola)

Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
Labour for laying dry graded Bhama khora or stone filter under Brick Pitching or Boulder Pitching in slope or upon including light ramming etc. all complete as per approved design, specification and direction of E.I.	cum	As Per				Appendix 1		
							228.79 205.93	2147. 41
								491305.93 4,42,216 =
Procuring and Laying reinforced cement concrete pipe 12" for culverts on first class bedding of granular material in single row including fixing collar with concrete mortar 1:2 bn excluding excavation, Protection Works, backfilling, concrete and masonry	M	0	2.50M	0	0			
Sand filling with Approved Materials seposited at site from roadway cutting and excavation from drain and foundation of other streecture graded and compected as per Technical Specification	M3	0						
TOTAL (in Re.)								491306.00
Total Rs-								491500.00 4,42,200 =

Junior Engineer,
Rural Works Department,
Works Section, Ghorasahan

Assistant Engineer,
Rural Works Department,
Works Sub Division, Ghorasahan

Executive Engineer,
Rural Works Department,
Works Division, Ghorasahan

Post Facto T.A./TS is accorded for Rs. 4,42,200 =

(.....crore.....Four.....lacs.....Forty Two.....thousand.....Two.....hundred.....) only.

S.E. (R.W.D.)
works Circle
Motihari

Doni
29-4-21

Name of Work : - Estimate for Emergent Repair of Road breaches (Damaged by Flood) for *Chharsahon*

Bakulia path to Bakulia ward No -06 (Saw Tola)

Appendix - 1

Measurement for surfacing the Breach with Brick Bats Filling

Sl. No.	Chainage Km	Length (M)	Avg. Width In Meter	Avg. Depth In Meter	Quantity (Cum)
1	127 M	23M	2.44 M	0.49 M ^{0.3}	27.49 CUM <i>16.83</i>
2	245 M	180 M	3.05 M	0.30 M	164.70 CUM
3	462 M	40 M	3.05 M	0.30 M <i>0.20</i>	36.60 CUM <i>24.40</i>
				TOTAL	228.79 CUM <i>205.93</i>

205.93

Sechuley
22/12/2020

Junior Engineer,
Rural Works Department,
Works Section, *Chharsahon*

Joseph
22/12/2020

Assistant Engineer,
Rural Works Department,
Works Sub Division, *Chharsahon*

JP
23/12/2020

Executive Engineer,
Rural Works Department,
Works Division, *Chharsahon*