




Name of Work:- Estimate for Repair of Road breaches (Damaged by Flood) for Motorability in L051- R.E.O. Lakhaura  
Adapur Road - Gamhariya Kala (BR-11R-307) For year 2020.

Head - 2245 Length-3.74KM


SI No.	Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Earth work in Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting Only and as per Technical Specification Clause 302.3	cum	As Per	I		Appendix	1590.343	412.47 302.42	655967.37 6,08,177.10
2		Providing & Laying dry graded Brick Bats including light ramming etc. all complete as per approved design, specification and direction of E/L.	cum	As Per	II		Appendix	178.79	2116.22	378356.33
3		Providing and laying reinforced cement concrete pipe NP3 for Cross Drainage 1000mm dia	RM	1Row x2Nos x2.50M=	5M			5.000	4032.75	20163.76
TOTAL (in Rs.)										1054487.46
Say Rs									1054000.00	10,06,698

  
Junior Engineer,  
Rural Works Department,  
Works Section, Adapur

  
Assistant Engineer,  
Rural Works Department,  
Works Sub Division, Adapur

  
Executive Engineer,  
Rural Works Department,  
Works Division, Raxaul

Post facto A.T.S is accorded for Rs. 10,06,700.00  
(Ten crore Ten lacs Six thousand  
Seven hundred only.)

  
S.E. (R.W.D.)  
works Cir.  
Motihari  
29.12.20