

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधुबनी।

पत्रांक - 1259313

दिनांक : 25.05.2021

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मधुबनी

अभियंता अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मधुबनी

विषय:- ग्रामीण कार्य विभाग, कार्य प्रमंडल, दर्जा-2 के अधीन रिकमांडा एव मनीगाछी प्रखंड में वर्ष 2020 में बाट/अविवृष्टि से क्षतिग्रस्त 101 जमी/पुलों में कारगरे मरु पुनर्स्थापन कार्य से संबंधित पथों का प्रावकलन के संबंध में।

प्रस्ताव:- मजदीद का पत्रांक-871 अगुठ दिनांक-10.04.2021

महोदय, उपरोक्त विषयक प्रारंभिक पत्र से प्राप्त यातायात पुनर्स्थापन के निम्नांकित प्रावकलन को गठित

जीव दल द्वारा जीवोपरान्त आवश्यक कार्रवाई हेतु समिपित की जाती है। विवरणी निम्न प्रकार है:-

Sl No	Block	Name of Road	Length (KM)	Qty. (Brick Bats) (M3)	Remarks
1	Manegachhi	Ashek Paper Mill Chakkari to Bideswar Sthan road	9.150	650.160	
2	Manegachhi	PMGSY Path Vihari to S.H. 67 Bhatpara road	1.970	315.940	
3	Manegachhi	PMGSY Road Vihari to Mithanahat tola	0.530	351.710	
4	Manegachhi	Tola to Bhatra	1.170	257.390	
5	Manegachhi	Lahoria State Boring to Indrathar H.O. Road tak	1.215	277.840	
6	Manegachhi	PWD Path to Kivahat tola	1.100	168.340	
7	Manegachhi	PMGSY road to Kivahat Bhatpara	1.600	73.760	
8	Manegachhi	PWD Patna Baharwa to Kanyar Bhatpara via Vahar tola	3.240	694.930	
9	Manegachhi	Lahoria R.V. Station to Sonpur via road	1.500	171.080	
10	Manegachhi	PWD Path Katma Baharwa to Bhatra tola	1.600	250.920	
11	Manegachhi	Bhatra tola Jagadishpur to Modin tola Jagadishpur	0.770	85.490	
12	Manegachhi	Tola to Bhatra	1.027	103.020	
13	Manegachhi	PWD road Bhatra to PWD road Kanyar tola	1.590	519.680	
14	Manegachhi	PMGSY Bhatra to Panchgachhi	1.650	226.500	
15	Manegachhi	R.O. road to Bhatra tola	1.170	444.500	
16	Manegachhi	Upin Majra chok to Amritsar road	3.800	289.330	
17	Manegachhi	PMGSY Path to Larkur Mahadali tola road	1.330	88.230	
18	Manegachhi	PMGSY road Sakhar to Khatwa Secma	0.500	237.750	
19	Manegachhi	PWD road Bhatra to Kanakpur	1.030	138.520	
20	Manegachhi	PWD Sasvaha Deykhar to Danji Masul tola via Refaral Hospital tak	1.500	638.430	
21	Manegachhi	Tola Brahmapara to Sakhar road	2.440	243.010	
22	Manegachhi	PMGSY Path to Larkur Brahmapara tola	1.050	429.000	
23	Manegachhi	Sakhar tola to School	2.500	559.620	
24	Manegachhi	R.O. road to Kanyar Mulla School Chakkari tola	1.090	679.100	
25	Manegachhi	Makhar tola to Bideswar Bhatpara Athan	3.200	472.180	
26	Manegachhi	PMGSY Sadak to Paswan tola	1.000	286.170	
27	Manegachhi	Prantik Vahar tola to Mushari H.O. via Vahar School tak	2.000	481.430	
28	Manegachhi	Manna Bahar Paswan tola to Makhar tola	1.110	341.800	

checked

Name of Road:-	T04 to Barha
----------------	--------------

BLOCK :-	Manigachhi
-----------------	-------------------

District:-	Darbhanga
------------	-----------

SUB HEAD : BRICK BATS

Laying & Distribution of Brick bats on affected Road portion as per specification to meet the required slope and proper light Ramming from a specified lead as per direction of E/I.

SI No	Chainage (in M)		Nos.	Length (m)	Width (Avg.) (m)	Height/Thickness (Avg.) (m)	Quantity	Rate (In Rs.)	Amount (In Rs.)
	From	To							
Superintending Engineer PWD, Works Circle, Darbhanga		150	1	20.00	1.50	0.25 0.60	7.50 18.00	1867.76	33620.00
			1	12.00 28.00	1.50	0.75	13.50 31.50	1867.76	58834.00
		350	1	6.00	0.60	0.30	1.08	1867.76	2017.00
		450	1	17.00 20.00	0.90+1.50 2	1.80 2	24.18 32.40	1867.76	60515.00
		500	1	15.00	3.5+4.50 4.50+6.50 2	1.50 2	78.00 136.10	1867.76	254202.00
			1	24.00 30.00	0.90	0.90	19.44 24.30	1867.76	45387.00
		650	1	12.00	0.60	0.45	3.24	1867.76	6052.00
		850	1	37.00	0.60	0.75	16.65	1867.76	31098.00
		900	1	42.00	0.50	0.90	18.90	1867.76	35301.00
		1000	1	4.00	3.5+4.50 4.50+6.50 2	1.50 2	21.60 35.20	1867.76	65745.00
			1	15.00	0.90	0.60	8.10	1867.76	15129.00
			2	3.00	1.75	1.80	18.90	1867.76	35301.00
		1050	1	3.00	4.50	0.90	12.15	1867.76	22691.00
			1	82.00 115.00	0.75	0.45 0.90	27.63 28.01	1867.76	144985.00

Superintending Engineer

Kohlensäure

$\text{Rs } 5.59.892 = \dots$