

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधुबनी।
पत्रक - 1259313

दिनांक : 25.05.2021

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मधुबनी

अभियंता अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मधुबनी

विषय:- ग्रामीण कार्य विभाग, कार्य प्रमंडल, दर्जा-2 के अधीन रिकमांडा एव मनीगाछी प्रखंड में वर्ष 2020 में बाट/अविवृष्टि से क्षतिग्रस्त 101 जमी/पुलों में कारगरे मदे पुनरुद्धारण कार्य से संबंधित पथों का प्राकलन के समय में।

प्रमाण:- मधुबनी का पत्रक-871 अगुठ दिनांक-10.04.2021

महाराज,

उपरोक्त विषयक प्रासंगिक पत्र से प्राप्त यातायात पुनरुद्धारण के निम्नांकित प्राकलन को गठित

जीव वल द्वारा जीवोपरान्त आवश्यक कार्रवाई हेतु समितित की जाती है। विवरणी निम्न प्रकार है:-

Sl No	Block	Name of Road	Length (KM)	Qty. (Brick Bats) (M3)	Remarks
1	Manegachhi	Ashok Paper Mill Chakkar to Bideswar Sthan road	9.150	650.160	
2	Manegachhi	PMGSY Path Vihari to S.H. 67 Bhatpara road	1.970	315.940	
3	Manegachhi	PMGSY Road Vihari to Mithanahat talu	0.530	351.710	
4	Manegachhi	Tola to Bhatra	1.170	257.390	
5	Manegachhi	Lahoria State Boring to Indrathar H.O. Road tak	1.215	277.840	
6	Manegachhi	PWD Path to Kivahat talu	1.100	168.340	
7	Manegachhi	PMGSY road to Kivahat Bhatpara	1.600	73.760	
8	Manegachhi	PWD Patna Baharwa to Ramgarh Bangala via Yadav talu	3.240	694.930	
9	Manegachhi	Luhana R.V. Station to Sonpur via road	1.500	171.080	
10	Manegachhi	PWD Path Katma Baharwa to Balha tal	1.600	250.920	
11	Manegachhi	Bachhat talu Jagadishpur to Modhat talu Jagadishpur	0.770	85.490	
12	Manegachhi	Tola to Bhatra	1.027	103.020	
13	Manegachhi	PWD road Balha to PWD road Kaimal	1.590	519.680	
14	Manegachhi	PMGSY Barha to Panchgachhi	1.650	226.500	
15	Manegachhi	R.O. road to Bahharhat talu	1.170	444.500	
16	Manegachhi	Upin Majra Chakkar to Amritnagar road	3.800	289.330	
17	Manegachhi	PMGSY Path to Larkur Mahadali talu road	1.330	88.230	
18	Manegachhi	PMGSY road Sakhar to Khatua Secma	0.500	237.750	
19	Manegachhi	PWD road Bahharhat to Kanakpur	1.030	138.520	
20	Manegachhi	PWD Sasvaha Deykhar to Danji Masul talu via Refaral Hospital talu	1.500	638.430	
21	Manegachhi	Tola Brahmapara to Sakhar road	2.440	243.010	
22	Manegachhi	PMGSY Path to Larkur Brahmapara talu	1.050	429.000	
23	Manegachhi	Sahant talu to School	2.500	559.620	
24	Manegachhi	R.O. road to Kaimal Middle School Chakkar talu	1.090	679.100	
25	Manegachhi	Makhar talu to Bideswar Bhatpara Athan	3.200	472.180	
26	Manegachhi	PMGSY Sadak to Paswan talu	1.000	286.170	
27	Manegachhi	Pradhat Yadav talu to Mushari H.O. via Vihari School talu	2.000	481.430	
28	Manegachhi	Manna Bahara Paswan talu to Makhar talu	1.110	341.800	

Estimate of Temporary Restoration of Flood affected Road

Name of Road:- PWD Patma Bahurwa to Rampur Bangala Tola, Yadav Tola

BLOCK :- Manigachhi

District:- Darbhanga

SUB HEAD : BRICK BATS

Laying & Distribution of Brick bats on affected Road portion as per specification to meet the required slope and proper light Rammimg from a specified lead as per direction of E/I.

SI No	Chainage (in M)		Unit	Nos.	Length (m)	Width (Avg.) (m)	Height/Thickness (Avg.) (m)	Quantity	Rate (In Rs.)	Amount (In Rs.)
	From	To								
			Cum	1	100.00	0.60	0.30	18.00	1867.76	33620.00
			Cum	1	32.00	1.50	0.60	28.80	1867.76	53791.00
			Cum	1	35.00	0.90	0.60	18.90	1867.76	35301.00
			Cum	1	17.00	1.00	0.60	10.20	1867.76	19051.00
			Cum	1	100.00	0.75	0.75	56.25	1867.76	105062.00
			Cum	1	100.00	0.60	0.60	36.00	1867.76	67239.00
			Cum	1	22.00	1.00	0.30	6.60	1867.76	12327.00
			Cum	1	5.00	5.00	1.80	45.00	1867.76	84049.00
			Cum	1	2.00	4.00	1.50	12.00	1867.76	22413.00
			Cum	1	4.00	4.00	0.75	12.00	1867.76	22413.00
			Cum	1	8.00	4.00	0.90	28.80	1867.76	53791.00
			Cum	1	31.00	1.80	0.75	41.85	1867.76	78166.00
			Cum	1	56.00	1.50	1.20	100.80	1867.76	188270.00
			Cum	1	5.00	5.00	1.20	30.00	1867.76	56033.00
			Cum	1	2.00	4.00	0.80	6.40	1867.76	11954.00
			Cum	1	27.00	5.00	1.95	315.90	1867.76	590025.00
			Cum	1	5.00	1.50	0.90	6.75	1867.76	12607.00
			Cum	1	9.00	2.00	0.90	16.20	1867.76	30258.00
			Cum	1	9.00	1.50	0.75	10.13	1867.76	18911.00
			Cum	1	11.00	1.50	0.75	12.38	1867.76	23114.00
			Cum	1	2.00	4.00	0.90	7.20	1867.76	13448.00
			Cum	1	27.00	1.50	0.60	24.30	1867.76	45387.00
			Cum	1	5.00	4.50	0.90	20.25	1867.76	37822.00

				1	18.00	(4.50+3.50) 1.50	CLY. 80		
	2300	Cum	1	1	18.00	1.50	121.50	1867.76	226933.00
		Cum	1	1	5.00	1.50	33.75	1867.76	63037.00
	2550	Cum	1	1	5.00	2.10	4.73	1867.76	8825.00
		Cum	1	1	9.00	1.50	0.75	1867.76	18911.00
	2650	Cum	1	1	6.00	0.90	1.62	1867.76	3026.00
		Cum	1	1	4.00	0.90	2.16	1867.76	4034.00
	2800	Cum	1	1	5.00	1.50	3.75	1867.76	7001.00
		Total=			666.00		1042.38		1946819.00
							694.93	Add GST @ 12%	233618.00
								Add Labour Cess @ 1%	49468.00
								Add SF @ 10% On Material Cost	110900.00
								Total Amount in Rs. =	2310705.00
								Total Say Amount in Rs. =	2310705.00

Assistant Engineer

RWĐ (W) Division, Darbhanga-2

RWD (W) Division, Darbhanga-2

RWD (W) Division, Darbhanga-2

checked by

জিয়া
T. E

19/4/22

12/59/21

117

કાર્યવાહક: જાનિજીબા, આવા વિગતોમાં કમ્પેન્સેશન નથી.

E.E

[illegible]

— En 11/3/18 Ed

R — Post-Feeto T/A 78 R 15,40,568 = Rupees fifteen —
— ~~hree~~ forty thousand five hundred sixty-eight only
(@ 2.5.2)

Q27.05.21

Superintending Engineer

o/RWD, Works Circle, Darbhanga

Karlsruhe