

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधुबनी।

पत्रांक:- 1286 3153

दिनांक:- 28.05.2021

प्रेषक,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मधुबनी

सेवा में,

अधीक्षण अभियंता
ग्रामीण कार्य विभाग,
कार्य अंचल, दरभंगा।

विषय:-

ग्रामीण कार्य विभाग, कार्य प्रमंडल, दरभंगा-2 के अधीन केवटी प्रखंड में वर्ष 2020 में बाढ़/अतिवृष्टि से क्षतिग्रस्त 10 पथों/पुलों में कराये गये पुर्नस्थापन कार्य से संबंधित पथों का प्राक्कलन के संबंध में।

प्रासंग:-

भवदीय का झापाक-872 दिनांक-10.04.2021

महाराज,

उपरोक्त विषयक प्रासंगिक पत्र से प्राप्त यातायात पुर्नस्थापन के निम्नांकित प्राक्कलन को गठित

जॉच दल द्वारा जॉचोपरान्त आवश्यक कार्रवाई हेतु सभिर्पित की जाती है। विवरणी निम्न प्रकार है:-

Sl No	Block	Name of Road	Length (KM)	Qty. (Brick Bats) (M3)	Remarks
1	Keoti	T04 Asrafpur (Milki) to Mohanmnapar	4.450	182.390	
2	Keoti	Kyam Chak to Dhaniyanaha	0.825	1590.500	
3	Keoti	Pindaruch to Kothiya Ghat	2.500	405.000	
4	Keoti	Jalwara to Kothiya Road	2.500	470.440	
5	Keoti	NH 105 Pathara to Khirama Bazar	0.350	38.150	
6	Keoti	REO road to Chandhi	2.850	95.000	
7	Keoti	L058 PMGSY Md. Dani to Bajitpur	5.200	75.000	
8	Keoti	NH 105 Dome to Shiso	8.000	171.120	
9	Keoti	REO Road Khirma to Sadik Muslim tola	1.165	173.370	
10	Keoti	Bariol to Kahariya	2.400	328.370	
Total:			30.240	3529.340	

अनु०:- यथोक्त

विश्वासभाजन

कार्यपालक अभियंता,

ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधुबनी।

Estimate of Temporary Restoration of Flood affected Road

Name of Road:- REO Road to Chandi

BLOCK :- Keoti

District:- Darbhanga

SUB HEAD : BRICK BATS

Laying & Distribution of Brick bats on affected Road portion as per specification to meet the required slope and proper light Raining from a specified lead as per direction of I/L.

Sl No	Challange (in M)		Unit	Nos.	Length (m)	Width (Avg.) (m)	Height / Thickness (Avg.) (m)	Quantity	Rate (in Rs.)	Amount (in Rs.)
	From	To								
		750	Cum	1	2.50	$\frac{4.00+3.50}{2}$	$\frac{1.80+2.20}{2}$	49.08 62.75	1895.36	120829.00
			Cum	1	4.00	$\frac{4.00+3.50}{2}$	$\frac{1.90+2.30}{2}$	30.80 28.00	1895.36	53070.00
			Cum	1	3.00	$\frac{2.50+4.50}{2}$	$\frac{2.20+1.80}{2}$	18.00	1895.36	34116.00
			Total		15.50			49.75 97.88		206015.00
										24962.00
										2080.00
Add Labour Cess @ 1%										2080.00
Add SF @ 10% On Material Cost										11666.00
Total Amount in Rs. =										246723.00
Total Say Amount in Rs. =										246723.00

Junior Engineer

RWD (W) Division, Darbhanga-2

Assistant Engineer

RWD (W) Division, Darbhanga-2

Executive Engineer

RWD (W) Division, Darbhanga-2

GENERAL ABSTRACT OF COST

Name of Road:- RFO Road to Chandi

Actual Length of Road 2.850 KM

TOTAL FLOOD AFFECTED LENGTH

Sl No	DESCRIPTION	Unit	Total Quantity	Rate (In Rs.)	Amount (In Rs.)
1	Laying & Distribution of Brick bats on affected Road portion as per specification to meet the required slope and proper light running from a specified lead as per direction of	Cum	109.75 97.88	1,895.36	208015.00 $185,518 = 10$
					Total= 208015.00
				Add GST @ 12%	24962.00
				Add L.Cess @ 1%	2080.00
				Add Seigniorage Fee On material Cost	11666.00
				Grand Total=	246723.00

If

AE

EE

Superintending Engineer
S.W.D. Works Circle, Darbhanga

$$1790.10$$

• Three types of neurons -

Find fare $\frac{7}{8}$ for £2.20, 0.40 = 10 (Rupees two less -

1) Wiederholung der Kontrollen der IS für 100-80-90-80-90-80-90-80
die für die Wiederholung der Kontrollen der IS für 100-80-90-80-90-80-90-80