

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधुबनी।

पत्रांक:- 1286 315

दिनांक:- 28.05.2021

प्रेषक,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मधुबनी

सेवा में,

अधीक्षण अभियंता
ग्रामीण कार्य विभाग,
कार्य अंचल, दरभंगा।

विषय:-

ग्रामीण कार्य विभाग, कार्य प्रमंडल, दरभंगा-2 के अधीन केवटी प्रखंड में वर्ष 2020 में बाढ़/अतिवृष्टि से क्षतिग्रस्त 10 पथों/पुलों में कराये गये पुर्नस्थापन कार्य से संबंधित पथों का प्राक्कलन के संबंध में।

प्रासंग:-

भवदीय का झापाक-872 दिनांक-10.04.2021

महाराज,

उपरोक्त विषयक प्रासंगिक पत्र से प्राप्त यातायात पुर्नस्थापन के निम्नांकित प्राक्कलन को गठित

जॉच दल द्वारा जॉचोपरान्त आवश्यक कार्रवाई हेतु सभिर्पित की जाती है। विवरणी निम्न प्रकार है:-

Sl No	Block	Name of Road	Length (KM)	Qty. (Brick Bats) (M3)	Remarks
1	Keoti	T04 Asrafpur (Milki) to Mohanmnapur	4.450	182.390	
2	Keoti	Kyam Chak to Dhaniyanaha	0.825	1590.500	
3	Keoti	Pindaruch to Kothiya Ghat	2.500	405.000	
4	Keoti	Jalwara to Kothiya Road	2.500	470.440	
5	Keoti	NH 105 Pathara to Khirama Bazar	0.350	38.150	
6	Keoti	REO road to Chandhi	2.850	95.000	
7	Keoti	L058 PMGSY Md. Dani to Bajitpur	5.200	75.000	
8	Keoti	NH 105 Dome to Shiso	8.000	171.120	
9	Keoti	REO Road Khirma to Sadik Muslim tola	1.165	173.370	
10	Keoti	Bariol to Kahariya	2.400	328.370	
Total:			30.240	3529.340	

अनु०:- यथोक्त

विश्वासभाजन

कार्यपालक अभियंता,

ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधुबनी।

Estimate of Temporary Restoration of Flood affected Road

Name of Road:- REO Road Khirma to Sadik Muslim Tola

BLOCK :- Keoti

District:- Darbhanga

SUB HEAD : BRICK BATS

Laying & Distribution of Brick bats on affected Road portion as per specification to meet the required slope and proper light Ramming from a specified lead as per direction of E/L.

SI No	Chainage (in M)		Unit	Nos.	Length (m)	Width (Avg) (m)	Height/Thickness (Avg) (m)	Quantity	Rate (In Rs.)	Amount (In Rs.)
	From	To								
		10	Cum	1	4.50	$\frac{3.50+4.50}{2}$	$\frac{0.80+1.20}{2}$	18.00	1895.36	34116.00
		20	Cum	1	15.00	2.50	0.40	15.00	1895.36	28430.00
		40	Cum	1	5.00	$\frac{3.50+4.50}{2}$	$\frac{0.50+0.70}{2}$	12.00	1895.36	22744.00
		150	Cum	1	7.00	$\frac{3.50+4.00}{2}$	$\frac{0.40+0.60}{2}$	13.13	1895.36	24877.00
		200	Cum	1	4.00	$\frac{3.25+3.75}{2}$	$\frac{0.40+0.80}{2}$	8.40	1895.36	15921.00
			Cum	1	6.00	1.50	0.45	4.05	1895.36	7676.00
			Cum	1	3.50	2.75	0.55	5.29	1895.36	10034.00
		470	Cum	1	24.00	$\frac{6.00+4.00}{2}$	$\frac{0.50+0.50}{2}$	54.20	1895.36	136466.00
			Cum	2	4.00	1.50	0.75	9.00	1895.36	17058.00
			Cum	1	8.00	$\frac{4.00+3.00}{2}$	$\frac{0.60+0.90}{2}$	21.00	1895.36	39803.00

cf 159.87

159.87

	1100	Cum	1	13.00	$\frac{3.50+4.00}{2}$	$\frac{0.40+0.60}{2}$	24.38	1895.36	46209.00
		Cum	1	4.00	3.50	0.45	6.30	1895.36	11940.00
		Cum	1	6.00	3.00	0.40	7.20	1895.36	13647.00
		Total=		104.00			215.75		40892.00
							173.37	Add GST @ 12%	49071.00
								Add Labour Cess @ 1%	4089.00
								Add SF @ 10% On Material Cost	22934.00
								Total Amount in Rs.=	485015.00
								Total Say Amount in Rs.=	485015.00

[Signature]
15/11/21

[Signature]
17.12.21

[Signature]
1/12/21

Junior Engineer
RWD (W) Division, Darbhanga-2

Assistant Engineer
RWD (W) Division, Darbhanga-2

Executive Engineer
RWD (W) Division, Darbhanga-2

GENERAL ABSTRACT OF COST

Name of Road:- REO Road Khirma to Sadik Muslim Tola

Actual Length of Road **1.165 KM**

TOTAL FLOOD AFFECTED LENGTH **0.104 KM**

Sl No	DESCRIPTION	Unit	Total Quantity	Rate (In Rs.)	Amount (In Rs.)
1	Laying & Distribution of Brick bats on affected Road portion as per specification to meet the required slope and proper light Ramming from a specified lead as per direction of	Cum	173.37 215.75	1,895.36	328599.00 408921.00
Total=					408921.00 328599.00
Add GST @ 12%					49071.00 39432.00
Add L.Cess @ 1%					4089.00 3286.00
173.37 x 1063 x 107. Add Seigniorage Fee On material Cost					22934.00 18429.00
Grand Total=					485015.00 389746.00

JE

AE

EE

कार्निवाल ऑफिसर को को दिने कार्य सम्पन्न करने का फाईल 1286 अतः दिनांक-28/05/21 के द्वारा जी.व. प्रविष्टि के अन्तर्गत
 फाईल - फाईल T/A ₹ 3,89,746.00 / Rupees Three lacs -
 - eighty nine thousand seven hundred forty six only

01.06.21
Superintending Engineer
 RWD, Works Circle, Darbhanga
 01/06/21