

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधुबनी।

पत्रांक:- 1286 3153

दिनांक:- 28.05.2021

प्रेषक,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मधुबनी

सेवा में,

अधीक्षण अभियंता
ग्रामीण कार्य विभाग,
कार्य अंचल, दरभंगा।

विषय:-

ग्रामीण कार्य विभाग, कार्य प्रमंडल, दरभंगा-2 के अधीन केवटी प्रखंड में वर्ष 2020 में बाढ़/अतिवृष्टि से क्षतिग्रस्त 10 पथों/पुलों में कराये गये पुर्नस्थापन कार्य से संबंधित पथों का प्राक्कलन के संबंध में।

प्रासंग:-

भवदीय का झापाक-872 दिनांक-10.04.2021

महाराज,

उपरोक्त विषयक प्रासंगिक पत्र से प्राप्त यातायात पुर्नस्थापन के निम्नांकित प्राक्कलन को गठित

जॉच दल द्वारा जॉचोपरान्त आवश्यक कार्रवाई हेतु सभिर्पित की जाती है। विवरणी निम्न प्रकार है:-

Sl No	Block	Name of Road	Length (KM)	Qty. (Brick Bats) (M3)	Remarks
1	Keoti	T04 Asrafpur (Milki) to Mohanmmadpur	4.450	182.390	
2	Keoti	Kyam Chak to Dhaniyanaha	0.825	1590.500	
3	Keoti	Pindaruch to Kothiya Ghat	2.500	405.000	
4	Keoti	Jalwara to Kothiya Road	2.500	470.440	
5	Keoti	NH 105 Pathara to Khirama Bazar	0.350	38.150	
6	Keoti	REO road to Chandhi	2.850	95.000	
7	Keoti	L058 PMGSY Md. Dani to Bajitpur	5.200	75.000	
8	Keoti	NH 105 Dome to Shiso	8.000	171.120	
9	Keoti	REO Road Khirma to Sadik Muslim tola	1.165	173.370	
10	Keoti	Bariol to Kahariya	2.400	328.370	
Total:			30.240	3529.340	

अनु०:- यथोक्त

विश्वासभाजन

कार्यपालक अभियंता,

ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधुबनी।

Estimate of Temporary Restoration of Flood affected Road

Name of Road:- NH 105 Dome to Shiso

BLOCK :- Keoti

District:- Darbhanga

SUB HEAD : BRICK BATS

Laying & Distribution of Brick bats on affected Road portion as per specification to meet the required slope and proper light Running from a specified lead as per direction of E/I.

SI No	Chainage (in M)		Unit	Nos.	Length (m)	Width (Avg) (m)	Height/ Thickness (Avg) (m)	Quantity	Rate (In Rs.)	Amount (In Rs.)
	From	To								
		325	Cum	1	8.00	$\frac{1.4+1.60}{2}$	$\frac{1.10+1.35}{2}$	15.00	1840.16	27602.00
			Cum	1	11.00	$\frac{1.00+1.20}{2}$	$\frac{0.60+0.90}{2}$	9.08	1840.16	16709.00
			Cum	1	8.00	0.90	0.75	5.40	1840.16	9937.00
			Cum	1	11.00	1.10	0.75	9.08	1840.16	16699.00
			Cum	2	7.00	0.90	0.60	7.56	1840.16	13912.00
			Cum	1	30.00	$\frac{1.00+1.20}{2}$	$\frac{0.75+1.00}{2}$	28.88	1840.16	53144.00
			Cum	1	10.00	0.90	0.70	6.30	1840.16	11593.00
			Cum	3	3.00	0.80	0.60	4.32	1840.16	7949.00
			Cum	1	4.00	0.90	0.75	2.70	1840.16	4968.00
			Cum	2	3.00	0.70	0.50	2.10	1840.16	3864.00
			Cum	1	4.00	0.60	0.70	1.68	1840.16	3091.00
			Cum	1	4.00	0.80	0.50	1.60	1840.16	2944.00
			Cum	2	5.00	0.90	0.80	7.20	1840.16	13249.00
			Cum	1	10.00	1.25	1.00	12.50	1840.16	23002.00
			Cum	1	15.00	$\frac{1.80+1.20}{2}$	$\frac{0.60+0.90}{2}$	16.88	1840.16	31062.00
			Cum	3	3.00	1.10	1.00	9.90	1840.16	18218.00
			Cum	1	6.00	1.10	0.75	4.95	1840.16	9109.00
			Cum	1	8.00	0.90	0.90	6.48	1840.16	11924.00
			Cum	1	6.00	0.80	0.70	3.36	1840.16	6183.00
			Cum	1	10.00	3.00	0.60	18.00	1840.16	33123.00
			Cum	1	6.00	0.90	0.75	4.05	1840.16	7453.00

Co:159.12

