



ग्रामीण कार्य विभाग



(बिहार सरकार)

FS 7/A Copy

क्षतिग्रस्त पथ का नाम

Malin to Ghormohna.

(Estimated Cost:- ^{6.22} 6.53 Lakh)

Length = 1.80 km

ग्रामीण कार्य विभाग,
कार्य प्रमंडल- फुलपरास।

बिहार सरकार

Abstract Of Cost.

1. Restoration of Road embankment using Brick Bats.....etc....

$298.89 \text{ m}^3 @ \text{Rs. } 1840.16/\text{m}^3$

Rs. 550005.00

Add GST 12% = Rs. 66001.00

Add LC 1% = Rs. 5500.00

Add S F 10% of material cost

$(298.89 \text{ m}^3 \times \text{Rs. } 1063.00) \times 10\% = \text{Rs. } 31772.00$

Total Rs. 653278.00

Total Rs. 621,787.00

Handwritten signature and date: 11.09.2020

Handwritten signature and date: 11.09.20

Handwritten signature

सहायक अभियंता, आर. ए. वि. कार्य अथवा एन. डी. ए. नगरपालिका
- १। सैन्य, कुमपुरास दिनांक - 17/12/2020 के द्वारा समिति/अंग प्रभु
के आधार पर -

Post- Facto T/A 72 Rs. 6,21,787.00/रुपैया
- Six lac twenty, one thousand seven hundred
- eighty seven only.

Superintending Engineer

विहार सरकार

Detailed estimate For restoration of road From Malin to Ghormohna 2020.

1. Restoration of Road embankment using Brick Bats.....etc....

At Chantage 0.50 Km. to 1.800 Km. ✓

19.85m x (1.80+2.0) m/2 x (2.40+2.10) m/2	=84.86 m ³
5.60m x (3.50+3.60)m/2 x (2.40+2.10) m/2	=44.73 m ³ 35.784 m ³
3.10m x (1.85+2.05) m/2 x (1.50+2.05) m/2	=10.73 m ³
1.05m x (0.90+1.20) m/2 x (0.85+1.00) m/2	=1.16 m ³ 1.02 m ³
1.50m x (1.25+1.40) m/2 x (0.90+1.10)m/2	=1.99 m ³
5.95m x (3.10+3.20) m/2 x (1.50+1.60) m/2	=29.05 m ³
8.45m x (3.70+3.50) m/2 x (1.25+1.50) m/2	=47.15 m ³ 41.828 m ³
32.50m x (3.70+3.80) m/2 x (0.60+0.70)m/2	=79.22 m ³
Total	= 298.89 m ³ 284.484 m ³

21.09.2020
JE

21.09.20
m

21.09.20
m

Detailed estimate For restoration of road From Malin to Ghormohna
Under FDR 2020.