



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

FDR/MR



Maker To Dihi

DISTRICT	-	Chapra	
DIVISION	-	Sonpur	
BLOCK	-	Maker	
TOTAL LENGTH OF ROAD	-	1.700	KM
TOTAL COST OF CONSTRUCTION	-	2.661	Lac
TOTAL COST OF PROJECT	-	2.661	Lac

Agency: - Shri Narendar Kumar

Inspection Report for flood damage work

Date:

1. Name of PIUs- RWD, Works Div. Sonapur.

2. Name of Block/Road- Maker, Maker to Diki-Satgaria.

A. For Road

1. Damage Location/Chainage : 960-974M, & 1685-1695M

2. Damage Length : 24.00 M

3. Nature of Damage : Breach out of road. embankment

4. Details of Restoration :

i Material being used in Restoration

: B/Bals, g.s. & nichel
local sand

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

: flip B/Bals with
wheel, & B/Bals g.s. &
24.00 M

iv Restored Length

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AE/EE

15/12/20
AE

Signature

(Name of Inspector)

प्रमंडल का नाम :- ग्रामीण कार्य विभाग, कार्य प्रमंडल सोनपुर
कार्य का नाम :- सारण जिला अन्तर्गत मकर प्रखंड में मकर से डीही सिद्धांत तक बाढ़ से क्षतिग्रस्त (FDR) का पूर्ण स्थापन कार्य।
पथ की लम्बाई :- 1.700 कि०मी०
क्षतिग्रस्त पथ की लम्बाई :- 24.00 मी०
प्राक्कलित राशि :- 2.661 लाख

प्रतिवेदन

यह प्राक्कलन सारण जिला अन्तर्गत मकर प्रखंड में मकर से डीही सिद्धांत तक बाढ़ से क्षतिग्रस्त (FDR) का पूर्ण स्थापन कार्य का प्राक्कलन का तैयार किया गया। पथ में CH 960m To 974m (14m) और CH 1685m To 1695m (10m) में बाढ़ के पानी का अधिक करंट रहने के कारण पथ में भारी कटाव हुआ है, जिसके कारण पथ से आवागमन अवरुद्ध हो गया है।

प्रस्तावित प्राक्कलन में पथ के कटे हुए पथांश में Bricks Bats भरकर तथा उसके ऊपर GSB कार्य किया गया है। यह प्राक्कलन वर्तमान अनुसूचित दर पर तैयार किया गया है जिसकी स्वीकृति अपेक्षित है।

15/12/20
कनिष्ठ अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मकर

15/12/20
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मकर

15/12/20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, सोनपुर

GENERAL ABSTRACT OF COST FOR FDR OF ROAD

NAME OF ROAD:
DISTRICT
BLOCK
DIVISION
LENGTH OF ROAD (in Km)

Maker To Dihri *S. E. Chopra*
Chapra
Maker
Sonpur
1.700

Sl. No.	DESCRIPTION	Amount	1 % Labour Cess	12 % GST	GROSS AMOUNT (LACS)
FACT-A	INITIAL RECTIFICATION INCLUDING SURFACE RENEWAL				
1	EARTHWORK	0.057	0.001	0.007	0.065
2	BRICK BATS	1.126	0.011	0.135	1.272
3	Local Sand	0.145	0.001	0.017	0.164
3	GSB	0.430	0.004	0.052	0.486
4	Grill	0.316	0.003	0.038	0.357
4	Grills	0.280	0.003	0.034	0.317
TOTAL COST OF PROJECT IN LACS =		2.355	0.024	0.263	2.661

S. E. Chopra
15/12/20
Junior Engineer

S. E. Chopra
15.12.20
Asstt. Engineer

S. E. Chopra
Executive Engineer

T/A Approved for Rs. 2.66 Lacs.

SR
RWD

S. E. Chopra
S.E. Chopra

