



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



FDR

Road Name:- Nawada Panchayat me Mai stream ka Padd se to Pithi road Chamkani
Tastamth hote hue Dachhoni Nawada gram to Winte to la hai us path ka Roadwork
on work

DISTRICT	:	East Champaran	
DIVISION	:	Areraj	
BLOCK	:	Arerajgrampur	
TOTAL LENGTH OF ROAD	:	1.10 Km	12,99,794=0
PART-A TOTAL COST OF INTIAL RECTIFICATION IN SURFACE RENEUAL (including 1%labour cess , 12% GST & 10% Seignoirage Fee)	:		298953=0 Lac
TOTAL COST OF PROJECT	:		15,98,747=0 Lac

Submitted by :
Bihar Rural Road Development Agency
RWD (W) Division, Areraj

NAME OF ROAD: Nahada Panchayat mo-Mul sthan ke Pass se Jo Pith road charpam
Parimali kote hua Dakhini Nahada gram to ulah tola jate hai us Parh ke Registration
Work

DISTRICT: East Champaran
 BLOCK: Areraj
 DIVISION: Areraj
 LENGTH OF ROAD (in Km): 1.10 km

Sl No.	DESCRIPTION	AMOUNT (LAKHS)
PART-A	INITIAL RECTIFICATION INCLUDING SURFACE RENEWAL	
1	Sand Filling	
2	Drick Bat	99569=00
3	Granuler Subbase (G.S.B. CR.I)	586,519=00
	TOTAL OF INITIAL RECTIFICATION INCLUDING SURFACE RENEWAL	613,706=00
	TOTAL COST OF CONSTRUCTION	12,99,794=00

Labour cess @ 1%.

(+) Rs. 12,998=00

GST @ 12%.

(+) Rs. 155975=00

Add Seigniorage fee @ 10%.

(+) Rs. 129979=00

Rs. 15,98,747=00

20/10/20

RWD (W) Division, Areraj

AE 20.10.20

RWD (W) Division, Areraj

20/10/20
 EE

RWD (W) Division, Areraj

Post facto T.A./TS is accorded for Rs. 12,99,800=00

(.....crore.....Twelve.....Ninety Nine
lacs.....thousand
Eight
hundred.....) only.

30/12/20
 S.E. (R.W.D.)
 works Circle
 Motihari
30-12-20

Maintenance & Damaged Portion

Name & Road :- Narada Panchayat me Mai shan ka Pat se Jo Pich road Chauranahar Road, hse hse- Dakhni Narada gram to Nirth Tala Jati hai us Pat ka Restoration hse (For year 2020-2021)

DETAILED COST ESTIMATE

Sr. No	SDB Ref No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1	11.2	Local Sand Filling in Foundation Trenches as per drawing and technical Specification Clause 305.3.9	cum	1	As per calculation	8 ft	156.77	635=13	99569=00	
2	with the help of WRD 5.7.40	Providing and Laying Spreading Brick Bats in Cut Portion as Required Do All C Job	cum		as per Calculation Sheet	07	21	273.13	2147.40	586519=00
3		Plastering of SSB in II shed compacted soil of Path side etc 07 21						281.96	2176.57	613706=00
A) SUB TOTAL = 1,299,794=00										

RWD (W) Division, Arera

RWD (W) Division, Arera

RWD (W) Division, Arera

Measurement of Damaged Portion

Job Name :- Nawada Panchayat me Majisthan ke part se
Jo Petch road chauran taraf ki hoti hai Dakshini
Nawada Gram to Minti Tola Jati hai us path ka Restoration
Work (for year 2020-2021)

Length :- 1.10 Km

Block :- Areraj

providing & laying spreading brick bats
filling in cut portion with sand as required
etc & - do all complete job

$$1 \times 9.0m \times \frac{0.90 + 2.80}{2} \times 1.20m = 19.98m^3$$

$$2 \times 15.0m \times 2.50m \times 1.25m = 93.75m^3$$

$$2 \times 20.0m \times \frac{1.10 + 1.50}{2} \times 0.90m = 46.8m^3$$

$$1 \times 18.0m \times \frac{1.5 + 2.5}{2} \times 1.20m = 43.20m^3$$

$$1 \times 7.5m \times \frac{2.5 + 3.5}{2} \times 0.90m = 20.25m^3$$

$$1 \times 14.0m \times \frac{2.15 + 1.75}{2} \times 1.10m = 30.03m^3$$

$$1 \times 10.0m \times \frac{1.5 + 2.75}{2} \times 0.90m = 19.12m^3$$

$$273.13m^3 \quad 2147 = 40/m^3$$

$$@ Rs 125/m^3 \quad Rs 586,519 = 00$$

providing local sand filling in road
construction & pot ditches etc & - do
all complete job

$$Influp :- 2 \times 5 \times 30.0m \times 0.90 \times \frac{0.15 + 0.30}{2} = 60.75m^3$$

$$In ditches :- 10 \times 4.0m \times \frac{1.85 + 2.75}{2} \times 0.45 = 41.40m^3$$

20% Add for voids of brick bats :-

$$273.13m^3 \times \frac{20}{100} = 54.62m^3$$

$$156.77m^3$$

$$@ Rs 635 = 13/m^3 \quad Rs 99569 = 00$$

Constructing of granular sub base by well
graded material etc & - do job

$$1 \times 12.0m \times 3.0m \times 0.175 = 6.30m^3$$

$$2 \times 20.0m \times 1.75m \times 0.175m = 12.25m^3$$

$$2 \times 22.0m \times 1.85m \times 0.200m = 16.28m^3$$

$$1 \times 20.0m \times 2.75m \times 0.175m = 9.625m^3$$

$$1 \times 10.0m \times 3.50m \times 0.175m = 6.125m^3$$

$$1 \times 15.0m \times 2.25m \times 0.175m = 5.90m^3$$

$$C.O. \quad 56.48m^3$$

$$B/F \& \frac{1}{2} = 56.42 m^3$$

$$B/F R_s 686088 = \infty$$

$$1 \times 4 \times 30.0 m \times \frac{3.75 + 4.10}{2} \times 0.175 m = 82.42 m^3$$

$$1 \times 5 \times 30.0 m \times 4.05 m \times 0.175 m = 106.31 m^3$$


$$2 \times 7 \times 15.0 m \times \frac{1.25 + 0.75}{2} \times 0.175 m = 36.75 m^3$$

$$281.96 m^3$$

$$@ R_s 2176 = 57/m^3 R_s 613706 = \infty$$

$$R_s 12,99,794 = \infty$$


 20/10/20
 J. E. / RWD
 Areraaj


 20.10.20.
 A. E. / RWD
 Areraaj


 20/10/20
 E. E. / RWD
 Areraaj