

FDR

DISTRICT :- DARBHANGA

BLOCK :- HANUMANNAGR

Name of Raad :- Booth 1 & 2

Length of the Road:- 0.200 KM

Effective Length 0.200 KM

GENERAL ABSTRACT OF COST

Sl No.	Item of Work	Amount (in Rs.)
1	Cost for restoration	61,038.40 ✓
2	Add 12 % GST	7,324.61 ✓
3	Add Seigniorage	3,473.88 ✓
4	Add 1 % Labour Cess	610.38 ✓
	Total cost:-	72,447.27 ✓

14/12/2020
Junior Engineer
Hanumannagar

15/12/20
Assistant Engineer
Hanumannagar

15/12/20
Executive Engineer
R.W.D.(W) Division, Darbhanga-1

कार्यपत्रक अग्रिमार्ग, नगरका 19, कार्यपत्रक - 4, नगरका 1 पत्रक 542 अग्रिम
दिनांक 07/04/2021 के द्वारा समर्पित प्रविष्टि का आधार पर

Post-Fee to T/A for Rs 72,447 = 00 (Rupees Seventy two -
thousand Four hundred fortyseven only.)

09/04/21
Superintending Engineer
R.W.D. Works Circle, Darbhanga

Detailed estimate for making moterable road.

Name of Raad :- Booth 1 & 2
 BLOCK :- HANUMANNAGR
 DISTRICT :- DARBHANGA
 R.W.D. Works Division Darbhanga-1

Sl. No.	Item	Unit	No.	Length (m)	Avg. Breadth (m)	Avg. Depth / Height	Quantity	Rate	Amount
1	Labour and placing of brick bats with light raming including cost of brick bats by tractor	cum	From Booth 1						
			0.000 KM to 0.200 KM.						
			1	5.00	2.00	0.500	5.000		
			1	2.00	2.00	0.500	2.000		
			1	1.50	2.00	0.400	1.200		
			1	10.20	3.00	0.800	24.480		
						Total	32.680	1867.76	61038.4
									61038.4

[Signature]
 14/12/2020
 Junior Engineer
 Hanumannagar

[Signature]
 14/12/20
 Assistant Engineer
 Hanumannagar

[Signature]
 14/12/20
 Executive Engineer
 R.W.D.(W) Division, Darbhanga-1