

FDR

DISTRICT :- DARBHANGA

BLOCK :- BAHERI

Name of Raad :- Samadhpora to Adharpur.


Length of the Road:- 2.300 KM.

Effective Length 0.130 KM.

GENERAL ABSTRACT OF COST

Sl No.	Item of Work	Amount
		(in Rs.)
1	Cost for restoration	2,18,948.17
2	Add 12 % GST	26,273.78
3	Add 1 % Labour Cess	2,189.48
4	Seigniorage Fee	12,461.02
Total cost:-		2,59,872.45


Say Rs 2,59,872 =⁰⁰/₁₀₀



15.12.2020
Junior Engineer
Bahadurpur


16/12/20
Assistant Engineer
Bahadurpur


Executive Engineer
R.W.D.(W) Division, Darbhanga-1

कार्यपालक अभियंता द्वारा कार्यविधि, कार्यप्रमंडल-फुलपलस के पत्रांक 542 अंशु 1
दिनांक 07/04/2021 / के द्वारा समाप्तित्त ऑन-य प्रतिवेदन के आधार पर।
Post-Facto T/A for Rs - 2,59,872 =⁰⁰/₁₀₀ (Rupees Two Lacs -
Fifty nine thousand Eight hundred Seventy two) only.


09.04.21
Superintending Engineer


RWD, Works Circle, Darbhanga
09/04/2021

Detailed estimate for making moterale road.

Name of Raad :- Samadhpura to Adharpur.
 BLOCK :- BAHERI
 DISTRICT :- DARBHANGA
 R.W.D. Works Division Darbhanga-1

Sl. No.	Item	Unit	No.	Length (m)	Av. Breadth (m)	Av. Depth / Height (m)	Quantity (cum)	Rate	Amount (In Rs.)
1	Labour and Placing Brick Bats with Light raming including cost of brick bats by tractor	cum	1	3.00	1.00	0.150	0.450		
			1	7.80	3.75	0.250	7.313		
			1	6.00	1.00	0.250	1.500		
			1	2.50	2.00	0.300	1.500		
			1	2.00	1.50	0.250	0.750		
			1	15.00	1.50	0.250	5.625		
			1	5.00	1.25	0.300	1.875		
			1	8.00	1.50	0.300	3.600		
			1	3.00	1.50	0.200	0.900		
			1	8.00	3.75	0.450	13.500		
			1	3.00	1.00	0.200	0.600		
			1	8.00	1.50	0.250	3.000		
			1	3.00	1.50	0.250	1.125		
			1	6.00	3.75	0.300	6.750		
			1	9.00	2.00	0.300	5.400		
			1	6.00	3.25	0.450	8.775		
			1	5.00	3.25	0.450	7.313		
			1	30.00	3.50	0.450	47.250		
							117.225	1867.76	218948.17

Bahani
 15.12.2020
 Junior Engineer
 Baheri

Am
 16/12/20
 Assistant Engineer
 Baheri

B
 15.12
 Executive Engineer
 R.W.D.(W) Division, Darbhanga-1