

RURAL WORKS DEPARTMENT
GOVT OF BIHAR



Name Of Work : PURI-CHOWK - PIPARA-KHURD

BLOCK

Parihar

FDR

Rs. ^{747350.00} ~~784467.00~~

Year - 2020-21

NAME OF CIRCLE - R.W.D., WORKS CIRCLE, SITAMARHI

NAME OF DIVISION - R.W.D., (W) DIVISION, SITAMARHI

प्रतिवेदन

कार्य का नाम :- पुरी चौक से पिपरा सुई पथ में

बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

प्राक्कलित राशि:- 747300.00

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक..... दिनांक
के अनुपालन में उक्त पथ के कार्य का प्राक्कलन तैयार किया गया है।

संलग्न प्राक्कलन 2020 के जुलाई माह में परिष्कृत प्रखंड में आई भीषण
बाढ़/अतिवृष्टि से क्षतिग्रस्त पुरी चौक से पिपरा सुई
पथ में बाढ़ से क्षतिग्रस्त भूगर्भीय मरम्मत FDR मद से कर यातायात चालू
करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत Rs. 747300.00 है, उक्त
पथ का निर्माण PMGSY/MMGSY/NABARD/GTSNY/SCP/MNP/MR
योजनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में है/नहीं है।

पथ के कटे (क्षतिग्रस्त) भाग में आवश्यकता अनुसार Brick-bats, Rabbish मरने भरकर MT
Sand Bag, बास बल्ला चबरी एवं लोकल कलू का प्रावधान किया गया है ताकि यातायात
चालू हो सकें।

प्राक्कलन के मदों का दर बर्तमान अनुसूचित दर से लिया गया है।

अभिषेक
कनीय अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रशाखा प.रि.ए.ए.

अभिषेक
सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमंडल प.रि.ए.ए.

अभिषेक
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल सीतामढ़ी।

DETAILED ESTIMATE FOR F.D.R.

General Abstract of Cost

Name of Road : PURI-CHOWK - PIPARA-KHURD
Length of Road : 0.0 KM
Block : Parihar
DISTRICT : SITAMARHI

S.No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	661333.00 694219.00
2	Labour cess @1%	6613.00 6942.19
3	GST @12%	79360.00 83306.28
	Total Cost of Road Repair	747306.00 784467.47
	Say	747300.00 784467.00

R 747300.00

[Signature]
JE

[Signature]
AE

[Signature]
EE

[Signature]
AE

[Signature]
Executive Engineer
R.W.D, Work Div. Pupri

Technically accorded for Rs 747300.00 (Rupees seven lakh forty seven thousand three hundred) only

E.E. Pupri *[Signature]*
योजना 244/10/21
मुबारकपुर दिनांक 09/5/21
को 344/पापिता

[Signature]
S.E.
R.W.D (W) Circle Sitamarhi

Schedule of Quantity

Name Of Work : PURI-CHOWK - PIPARA-KHURD

Block Parbat

S.No	OF ITEMS	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1		Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	401.00	0.00
2		Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.	477.43 501.17			0.00
		Less 20% for Voids	95.49 400.23			
			381.94 400.94	Cum	1546.60	598577.94 519845.51
3		Single bamboo palasiding / walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and struts 1.5 m apart longitudinally and providing brush wood as per drawing and technical specifications Clause 1302.5	0.00	m	172.62	0.00
4		Providing ,laying and placing empty cement bag filled with local sand including stitching with sutali etc. ----- do ----- do-----all complete job as per specification and direction of E/I.(Including Royalty and all Taxes)	0.00	no.	23.12	0.00
5		Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row with old available pipe	0.00	m	3158.89	0.00
6		Providing Quarry Material Rabbish for filling the voids in bricks bats -----do----- all complete job as per specification and direction of E/I.				
		Taking 20% of Brick Qty for Rabbish	95.49 100.23	Cum	742.00	70854.0 74373.03

Total 694218.54 - 661333.00
Say 694219.00


JE
25/12/20
JE


AE
25/12/20
AE


EE
28/12/20
EE


Details of Measurement of ditches filled by brick bats and rabbish

Name Of Work : PURI-CHOWK - PIPARA-KHURD								
					L	W	H	VOLUME
					8.00	5.00	1.20	48.00
					6.50	5.25	1.25 1.10	42.66 37.59
					11.00	6.00	1.50	99.00
					11.00	5.50 5.0	1.75	106.88 96.25
					8.00	1.50	0.75	9.00
					5.00	1.25	0.75	4.69
					5.00	1.50	0.80	6.00
					5.00	1.40	0.85	5.95
					15.00	6.00	2.00 1.90	180.00 171.00
					Total (in Cum)			577.43 501.17


 25.12.20
 CR


 25.12.20
 ME


 28/12/20


 30.12.20
 AB