

Abstract of Cost

NAME OF SCHEME : FDR 2020
NAME OF ROAD : Hayaghat B.H.Q to Aliyabad Path
DISTRICT : Darbhanga
BLOCK : Hayaghat
DIVISION : Darbhanga-1
LENGTH OF ROAD : 1.911km

Sl. No.	DESCRIPTION	AMOUNT
	RESTORATION WORK USING BRICK BATS	
	TOTAL COST OF WORK (Total quantity 154.815 m ³ @ RATE Rs 1867.76)	₹ 2,89,157.26
	ADD GST @ 12 %	₹ 34,698.87
	ADD LABOUR CESS @ 1 %	₹ 2,891.57
	ADD SEIGNIORANGE FEE ((Total quantity 154.815 x Rs 1063.00) x 10%)	₹ 16,456.83
	TOTAL COST	₹ 3,43,204.54

Say Total Rs. 3,43,205 = w ✓

14/12/20
JE
RWD

15/12/20
AE
RWD

15/12/20
EE
RWD

कार्यपालक अभियंता, ग्राह को वि०, कार्य प्रमंडल - फुलपरास को पराकृष्ट अंगु
दिनांक 08/04/2021 / के द्वारा समाप्त जो-य प्रतिवेदन के आधार पर।

Post-Facto T/A for Rs - 3,43,205 = w (Rupees Three
Lacs forty three thousand two hundred five) only.

09/04/21
Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2021

Detailed Estimate of Flood Damaged Road

Block:- Hayaghat
District:- Darbhanga

Name of Division:- Darbhanga I
Name of Work:- Hayaghat B.H.Q. to Alivabad Path
Name of Scheme:- FDR 2020
Length (km):- 19.1 km

Sl. No.	S.R. & No.	Items of Work	Details of Actual Measurement				Quantity
			No	Length	Breadth (average)	Depth (average)	
1	R.H.Q.R.	Providing and laying of Bricks bats with carriage by tractor loading with front end loader with light ramming etc all complete job					
			Particulars				
			1	4.50	3.75	1.00	16.875 ✓ m ³
		Chainage 0-300m	1	20.00	3.30	1.25	82.500 ✓ m ³
		Chainage 0-300m	1	28.00	3.30	0.60	55.440 ✓ m ³
		Chainage 0-300m					
		Total					154.815 ✓ m³

[Signature]
14/12/20
Junior Engineer

[Signature]
Asstt. Engineer

[Signature]
Executive Engineer