

FDR

DISTRICT :- DARBHANGA

BLOCK :- BAHERI

Name of Raad :- L037 BARCHHIA


Length of the Road:- 2.569 KM

Effective Length 0.149 KM.

GENERAL ABSTRACT OF COST

No.	Item of Work	Amount (in Rs.)
1	Cost for restoration	2,38,315.92 ✓
2	Add 12 % GST	28,597.91 ✓
3	Add Seigniorage	13,563.30 ✓
4	Add 1 % Labour Cess	2,383.16 ✓
Total cost:-		2,82,860.29 ✓



14.12.2022
Junior Engineer
Baheri


15.12.2022
Assistant Engineer
Baheri


Executive Engineer
R.W.D.(W) Division, Darbhanga-1

आदिपालक अमिषील, ग्राह का. वि. आदिप्रमाण-कृतपत्र का पत्रिका: 542 अ. 30
दिनांक: 07/04/2021 के द्वारा समिति जांच प्रतिवेदन के आधार पर —


Post-facto T/A for Rs. 2,82,860.00 (Rupees Two Lacs
eighty two thousand eight hundred sixty) only


09.04.21
Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2021

Detailed estimate for making moterable road.

me of Raad :- L037 BARCHHIA TO SHEKHPURA
 CK :- BAHERI
 RICT :- DARBHANGA
 D. Works Division Darbhanga-1

o	Item	Unit	No.	Length (m)	Breadth (m)	Depth / Height (m)	Quantity	Rate	Amount
	Labour and placing of brick bats with light raming including cost of brick bats by tractor	cum	From BARCHHIA						
			1.000 KM to 2.000 KM						
			1	15.00	3.50	0.450	23.625	/	
			1	14.50	3.40	0.400	19.720	/	
			1	29.00	3.50	0.250	25.375	/	
			1	17.00	4.00	0.300	20.400	/	
			1	14.00	3.50	0.350	17.150	/	
			1	13.50	3.65	0.250	12.319	/	
			1	11.80	3.18	0.240	9.006	/	
						Total	127.595	1867.76	238316
									238316


 14.12.2020
 Junior Engineer
 Baheri


 15/12/20
 Assistant Engineer
 Baheri


 15/12/20
 Executive Engineer
 R.W.D.(W) Division, Darbhanga-1