

Abstract of Cost

NAME OF SCHEME : FDR 2020
 NAME OF ROAD : L043 Hayaghat to gharari
 DISTRICT : Darbhanga
 BLOCK : Hayaghat
 DIVISION : Darbhanga
 LENGTH : ROAD 3.2

SL. No.	DESCRIPTION	AMOUNT
	RESTORATION WORK USING BRICK BATS	
	TOTAL COST OF WORK (Quantity 822.263 m ² @ RATE Rs 1867.76)	₹ 15,17,111.41
	ADD GST @ 12 %	₹ 1,82,053.37
	ADD LABOUR CESS @ 1 %	₹ 15,171.11
	ADD SE EN (10% SE FREE) Total quantity 822.263 x Rs 1068.00 (x 10%)	₹ 86,343.50
	TOTAL COST	₹ 18,00,679.39
		Total = ₹ 17,81,282 = 00

17/02/20
 RWD

17/02/20
 RWD

17/02/20
 RWD

परमाणु अंकित, 2170 कार्ड, कार्य-अंकित कुमारी का पत्र:- 542 अंकित
 दिनांक:- 07/04/2021 के द्वारा समिति-अंकित-परमाणु अंकित के अंकित -

Post-Feet T/A 78 Rs 17,81,282 = 00 (Rupees Seventeen thousand eight hundred eighty two only).

09-4-21
 Superintending Engineer
 RWD, Works Circle, Darbhanga
 09/04/2021

Detailed Estimate of Flood Damaged Road

Name of Division:- Darbhanga-1
 Name of Work:- 1043 Hayaghat to gharari
 Name of Scheme:- FDR 2020
 Length (in Km):- 3.250km

Block:- Hayaghat
 District:- Darbhanga

Sl. No.	SOR Sl. No.	Items of Work
1	6.61 WRD B.I.H.A.R.	Providing and laying of Bricks bats with carriage by tractor loading with front end loader with light ramming etc all complete job

Particulars	Details of Actual Measurement				Quantity (m ³)	
	No.	Length (m)	Breadth (average) (m)	Depth (average) (m)		
Chainage 000-200m	1	22.00	1.00	1.50	33.000	m ³
Chainage 200-400m	1	5.00	4.00	0.60	12.000	m ³
Chainage 400-600m	1	160.00	1.50	1.00	240.000	m ³
Chainage 600-700m	1	12.00	1.00	0.60	7.200	m ³
Chainage 600-700m	1	2.00	1.50	0.30	0.900	m ³
Chainage 600-700m	1	2.50	1.30	0.45	1.463	m ³
Chainage 600-700m	1	15.00	1.00	0.60	9.000	m ³
Chainage 600-700m	1	2.50	1.00	0.30	0.750	m ³
Chainage 1000-1250m	1	18.00	2.00	2.50	0.000	m ³
Chainage 1000-1250m	1	20.00	1.50	0.60	8.000	m ³
Chainage 1000-1250m	1	70.00	2.50		50.000	m ³
Chainage 1000-1250m	1	3.00	1.00		3.000	m ³
Chainage 2000-2350m	1	6.00	1.00		5.000	m ³
Chainage 2000-2350m	1	1.50	1.00	0.30	0.450	m ³
Chainage 2850-3000m	1	12.00	1.00	0.60	7.200	m ³
Chainage 3000-3250m	1	30.00	1.50	0.60	27.000	m ³
Chainage 3000-3250m	1	5.50	1.00	0.60	3.300	m ³
Total					341.25 m ³	

14/12/20
 Junior Engineer

Asstt. Engineer

Executive Engineer