



Abstract of cost for Restoration work of SH 54 Langar Chowk to Uttari Amba Siwan Tak after flood 2020.

Sl. No.	Item of work	Unit	Quantity	Rate	Amount
1	Supplying & filling of brick bats with manual compactiondo....do all complete job as per direction of E/I.				
	(a) Bricks bat	cum	108.86	1546.00	168297.56
	(b) Rubbish	cum	27.22	742.00	20197.24
Total					188494.80
Add 1% labour Cess					1884.95
Add 12% GST					22619.38
Grand Total					212999.12
Say Rs					213000.00


8-4-21

J.E



05.04.21

A.E.


8-4-21

यह प्रचलन अक्षीकरण अभियंता कार्य अंशुस सितामोही द्वारा वाहित
आवदिस (कार्यपासक अभियंता सितामोही के अर्थ प्रविषेण
254/29-1-21

Technically Approved for Rs 213000.00 (Rupees Two
Lakh Thirteen Thousand) only.


12/4/21

S.E.
R.W.D. (W) Circle
Sitamarhi

**Detailed Estimate of Restoration work of road from SH 54 Langar Chowk to Uttari
Amba Siwan Tak after flood 2020**

sl no. 1	Supplying & filling of brick bats with manual compactiondo....do all complete job as per direction of E/l.							
	from chainage in M	to chainage in M	length in M	width in M	depth in M		Quantity in CUM	
1	480	500	20.00	3.2	0.5		32.00	
2	565	593	28.00	3	0.3		25.20	
3	730	762	32.00	3.4	0.6		65.28	
4	810	826	16.00	3.4	0.25		13.60	
							136.08	
(a)							Brick Bats 80%	108.86
(b)							Rubbish 20%	27.22


5/4/21

J.E.


05-04-21

A.E.


5/4/21