Abstract of cost for Restoration work of Ojha Tola to Mahuawa Road after flood 2020.					
Sl. No.	Item of work	Unit	Quantity	Rate	Amount
1	Supplying & filling of brick bats with manual compaction ....do....do all complete job as per direction of E/I.				
	(a) Bricks bat	cum	188.16	1546.00	290895.36
	(b) Rubbish	cum	47.04	742.00	34903.68
			Total		325799.04
			Add 1% labour Cess		3257.99
			Add 12% GST		39095.88
			Grand Total		368152.92
			Say Rs		368150.00

J.E

A.E.

E.E

यह प्राक्कलन अधीक्षण अभियंता कार्य अंचल सीतामढ़ी द्वारा गठित जांचदल (कार्यपालक अभियंता सीतामढ़ी) के जाँच प्रतिवेदन 254/28-1-21

Technically Approved for Rs 368150=00 (Rupees Three lakh Sixty eight Thousand One hundred Fifty) only

14/4/21

S.E.
R.W.S.(W) Circle
Sitamarhi

Scanned with CamScanner

Detailed Estimate of Restoration work of road from Ojha Tola to Mahuawa Road after flood 2020							
sl no. 1	Supplying & filling of brick bats with manual compaction ....do....do all complete job as per direction of E/I.						
	from chainage in M	to chainage in M	length in M	width in M	depth in M		Quantity in CUM
1	60	340.00	280.00	2.8	0.3		235.20
							235.20
(a)						Brick Bats 80%	188.16
(b)						Local Sand/ Rubbish 20%	47.04

J.E.

A.E.