


Abstract of cost for Restoration work of road from Madhopur Chhata to Sunderpur Road after flood 2020

Sl. No.	Item of work	Unit	Quantity	Rate	Amount
1	Supplying & filling of brick bats with manual compactiondo....do all complete job as per direction of E/I.				
	(a) Bricks bat	cum	195.23	1546.00	301825.58
	(b) Rubbish	cum	48.81	742.00	36217.02
Total					338042.60
Add 1% labour Cess					3380.43
Add 12% GST					40565.11
Grand Total					381988.14
Say Rs					381980.00


J.E.


A.E.


S.E.

यह प्रापलसु अवस्थागत अभियंता कार्य अंचल स्तरीयमही कार्य
गठित अभियंता (कार्यप्राप्त अभियंता स्तरीयमही) के द्वारा
प्रतिबद्ध
254/29-1-21

Technically Approved for Rs 381980.00 (Rupees
Three lakh Eightyone Thousand Nine hundred
Eighty) only.


254/21

S.E.
R.W.D. (W) Circle
Sikarhi

Detailed Estimate of Restoration work of road from Madhopur Chhata to Sunderpur Road after flood 2020

sl no. 1	Supplying & filling of brick bats with manual compactiondo....do all complete job as per direction of E/I.							
	from chainage in M	to chainage in M	No.	length in M	width in M	depth in M		Quantity in CUM
1	800	816		16	3.00	0.45		21.60
2	1397	1422		25	3.50	0.45		39.38
3	1900	1945		45	3.00	0.45		60.75
4	4030	4048		18	3.45	0.6		37.26
5	6004	6038		34	3.50	0.45		53.55
6	6500	6520		20	3.50	0.45		31.50
							Total	244.04
(a)								Brick Bats 80%
(b)								Local Sand/ Rubbish 20%
								195.23
								48.81


J.E.


A.E.


J.E.