



GOVERNMENT OF BIHAR

NAME OF WORK:- Restoration work of Road Korha to
Morsanda

(FDR PART-A)

Restoration Length :- 187 M

Block:- Falka

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST


Rs. 29,98,485.00


**-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION**


ग्रामीण कार्य विभाग, कार्य प्रमंडल, कटिहार।
बाढ़/अतिवृष्टि से क्षतिग्रस्त पथों/पुलों की आपातकालीन मरम्मत हेतु जाँच प्रतिवेदन।
(वित्तीय वर्ष-2020-21)


Block - Falka

Sl No.	Name of District	Name of Division	Name of Road	Road Status	Length (In Km)	Estimated Cost For Restoration (In Lakh)	Remarks
1	2	3	4	5	6	7	8
1	Katihar	Katihar	Bharsia Korha Falka PWD Road to Mohammad Nagar	Completed	4.175	355163.00	Restoration Work Complete
2	Katihar	Katihar	Const. of road from Gopalpatti chauk to BHQ via Baburbanna Adiwasitola & Bintoli Singhia under Falka Block.	Completed	5.010	470366.00	Restoration Work Complete
3	Katihar	Katihar	Near Lakshmipur Marangi Tola To Mushari Tola	Ongoing	1.600	398613.00	Restoration Work Complete
4	Katihar	Katihar	Giriyama PWD road to morsanda more	Completed	2.400	1422974.00	Restoration Work Complete
5	Katihar	Katihar	Santhal Tola To Govindpur Diyara Mandal Tola	Completed	2.916	6452303.00	Restoration Work Complete
6	Katihar	Katihar	Korha to morsanda	Completed	9.800	2998485.00	Restoration Work Complete
Total :-						12097904.00	


 (ई० मृत्युंजय कुमार)
 कनीय अभियंता
 ग्रामीण कार्य विभाग
 कार्य प्रशाखा, फलका।


 (ई० विजय कुमार)
 सहायक अभियंता
 ग्रामीण कार्य विभाग
 कार्य अवर प्रमंडल, फलका।


 (ई० चन्द्रहास कुमार)
 कार्यपालक अभियंता
 ग्रामीण कार्य विभाग
 कार्य प्रमंडल, कटिहार।


 (ई० अम्यानन्द शर्मा)
 कार्यपालक अभियंता
 ग्रामीण कार्य विभाग
 कार्य प्रमंडल, मनिहारी।

तकनीकी प्रतिवेदन

योजना का नाम :- अतिवृष्टि एवं बाढ़ के कारण क्षतिग्रस्त "कोढ़ा से मोरसण्डा" पथ आकस्मिक मरम्मति कार्य (पार्ट-A)

क्षतिग्रस्त पथ की लम्बाई :- 187 मी०

प्राक्कलित राशि :- ₹0 29,98,485.00

योजना शीर्ष :- FDR (2245)

प्राधिकार :- सचिव, ग्रामीण कार्य विभाग, बिहार, पटना का पत्रांक-2789 दिनांक 21.08.2020

प्रतिवेदन


प्रस्तुत प्राक्कलन अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथ के पथांश का प्राक्कलन ₹0 29,98,485.00 मात्र के लिए ग्रामीण कार्य विभाग, कार्य प्रमंडल, कटिहार के द्वारा शीर्ष FDR के अन्तर्गत बनाया गया है।


पथ के आकस्मिक मरम्मति हेतु पथांशों में Brick Bats, बॉस पाईलिंग, चचरी, एवं खाली सिमेंट बैग में लोकल बालू भरकर बचाव का कार्य करते हुए यातायात पुर्नस्थापित किया गया है।


पथ मरम्मति कार्य का प्राक्कलन वर्तमान अनुसूचित दर एवं सामग्री की दुलाई निकटतम खदान से प्रावधान कर बनाया गया है। दर गणना में संवेदक लाभांश सम्मिलित नहीं हैं।

उक्त कार्य को विभागीय रूप से कराये जाने हेतु आदेश प्राप्त है (प्रति संलग्न) एवं प्रशासनिक स्वीकृति हेतु तकनीकी अनुमोदन अपेक्षित है।

प्रमाणित किया जाता है कि प्राक्कलन कार्य स्थल के अनुरूप है।


कनीय अभियंता,
फलका।


सहायक अभियंता,
ग्रा०का०वि०, कार्य अवर प्रमंडल,
फलका।


कार्यपालक अभियंता
ग्रा०का०वि०, कार्य प्रमंडल,
कटिहार।


NAME OF WORK:- Restoration work of Road Korha to Morsanda


Total Length :- 9.800 Km


Restoration Length :- 187 M

ABSTRACT OF COST


1	Cost of Emergent repair of road	Rs.	25,22,218.01
2	Add 1 % Labour Cess	Rs.	25,222.00
3	Add 12 % GST	Rs.	3,02,666.00
4	Add for Seigniorage Fee	Rs.	1,48,379.00
Total :-		Rs.	29,98,485.01
Say		Rs.	29,98,485.00



J.E.


A.E.
RWD, Sub-Division, Falka


E.E.
RWD (W) Div. Katihar

Technically approved for Rs 29,98,485.00 (Rupees twenty nine lacs ninety eight thousand four hundred eighty five) only.

checked by me

A.E.


SUPERINTENDING ENGINEER
R.W.D. WORK CIRCLE, PURNEA

NAME OF WORK:- Restoration work of Road Korha to Morsanda

Total Length :- 9.800 Km

Restoration Length :- 187 M

Sl. No.	ITEM OF WORKS					QTY	UNIT	RATE	AMOUNT	
1	Labour for filling empty cement bags with local sand, stitching the bags and placing including supply of sutti etc. all complete as per approved design, specification and direction E/I.									
	Total Sand Bag =					3345	Nos	32.14	1,07,508.30	
2	Providing and Laying of Brick Bats									
	Placing tractor at loading point loading with front end loader dumping ,turning for return trip exluding time for haulage and return tirp									
	15.0	x	3.20	x	2.60	=			124.80	
	15.0	x	3.20	x	2.20	=			105.60	
	15.0	x	3.00	x	2.10	=			94.50	
	15.0	x	4.20	x	2.20	=			138.60	
	15.0	x	3.00	x	2.60	=			117.00	
	15.0	x	3.20	x	2.10	=			100.80	
	15.0	x	3.20	x	2.20	=			105.60	
	15.0	x	3.00	x	2.10	=			94.50	
	15.0	x	3.00	x	2.10	=			94.50	
	15.0	x	1.80	x	2.30	=			62.10	
	30.0	x	2.70	x	2.30	=			186.30	
	7.0	x	1.10	x	1.30	=			10.01	
	Total					=	1234.31	cum	1,717.37	21,19,767.00
3	Labour for fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification and direction of E/I									
	990	No.	x	5	M	=			4950.00	
	Total					=	4950.00	M	47.58	2,35,521.00
4	Labour for fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification and direction of E/I									
	49	No	x	12	M	=			588.00	
	Total					=	588.00	M	24.71	14,529.48
5	Labour for fitting and and fixing split bamboo woven chachari in position with 20 swg G.I. wire of 75 mm to 100 mm long nails alternatively including cost of G.I. wire or nails complete job as per specification and direction of E/I.									
	1	No.	x	135	M x 1.50 M	=			202.50	
	Total					=	202.50	Sqm	221.69	44,892.23
	Total cost								Rs.	25,22,218.01

J.E. 20/10/20 20.10.2020

Executive Engineer
RWD. (W) Div. Katihar.