

ABSTRACT

Road name - Temporary Restoration of Road from Sonki Thana chauk to Lakhana


Block-DARBHANGA

RWD (W) DIVISION DARBHANGA -1


Road Actual Length - 1.65 KM

Effect Road Length 203.00 M.

S.No.	ITEM	UNIT	QUANTITY	RATE	AMOUNT (Rs)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I.	CUM	247.171 314.491	1867.76	461656 = 0 587394
	Add G.S.T. 12 %				70487 55399 = 0
	Add 1 % Labor cess				5874 4617 = 0
	Seigniorage Fee @1063.00/cum x0.10				33430 26274 = 0
	Total				697185 547946 = 0



J.E.

Work Section Darbhanga-2


A.E.

Work Sub-Division
Darbhanga


Rs-5,47,946 = 0


E.E.

RWD Darbhanga -1

कार्यपालक अभियंता आग का वि० कार्य प्रमाणित कुलपरास के पत्रांक 542 आनुं 1 दिनांक 07/04/2021 के द्वारा समाप्त जॉन प्रतिवेदन के आधार पर —

Post-Facto T/A for Rs-5,47,946 = 0 (Rupees Five Lacs forty seven Thousand nine hundred forty seven) only

1 
09.04.21
Superintending Engineer.
RWD, Works Circle, Darbhanga
09/04/2021

Detailed Estimate for Temporary Restoration of Sonki Thana chauk to Lakhana road for the year 2020 -21.

Block -Darbhanga

Total Restoration Length -203.00 M

R.W.D.[W] Division -Darbhanga -1

Length -1.65 km

S.N.	item	No.	Length (M)	Width(M)	Depth (M)(AV)	Quantity (cum)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I .					
	Chainage in M					
	100 M (at main road)	1	10.00	1.25	0.300	3.750
	To	1	6.60	2.25	0.225	3.341
		1	12.00	1.50	0.200	3.600
		1	8.50	1.50	0.200	2.550
		1	12.00	1.50	0.200	3.600
		1	7.20	1.60	0.225	2.592
	240	1	9.00	1.50	0.225	3.038
	115 (Towards Pond) to 251	1	136.00	$(0.60+1.50)/2$	1.500	214.200
		1	22.00	$(1.50+1.90)/2$	0.450	16.830
		1	9.50	1.25	0.300	3.563
		1	8.00	2.60	0.300	6.240
	Near platform	1	17.50	3.90	0.750	51.188
	Total Qty.					314.491

146.88

247.17

J.E.

A.E.

E.E.

RWD(W) Division Darbhanga -1