

Abstract of cost for Restoration work of Kanuani to Rampur Kesho Road after flood 2020.

Sl. No.	Item of work	Unit	Quantity	Rate	Amount
1	Supplying & filling of brick bats with manual compactiondo....do all complete job as per direction of E/I.				
	(a) Bricks bat	cum	181.07	1546.00	279934.00
	(b) Rubbish	cum	45.27	742.00	33590.00
	Total				313524.00
	Add 1% labour Cess				3135.00
	Add 12% GST				37622.88
	Grand Total				354281.88
	Say Rs				354280.00


J.E.


A.E.


S.E.

यह प्रावजन अक्षाण्ड अभियंता कार्य अंशसुही क्षाण्ड अभि
निधिद्वय (कार्यप्राण्ड अभियंता क्षाण्ड अभि) के अक्षि-प्राण्ड
254/29-1-21

Technically Approved for Rs 354280.00 (Rupees
Three hundred fifty four thousand Two hundred
Eighty) only.



12/4/21

S.E.
R.W.D.(W) etale
Bhawanahi

Detailed Estimate of Restoration work of road from Kanuani to Rampur Kesho Road after flood 2020.

sl no. 1	Supplying & filling of brick bats with manual compactiondo....do all complete job as per					
	from chainage in M	to chainage in M	length in M	width in M	depth in M	Quantity in CUM
1	500.00	565.00	65.00	3.2	0.3	62.4
2	1490.00	1517.00	27.00	3.2	0.4	34.56
3	2040.00	2120.00	80.00	3.25	0.2	52
4	2250.00	2315.00	65.00	2.9	0.2	37.7
5	2730.00	2794.00	64.00	3.1	0.2	39.68
						226.34
(a)	Brick Bats 80%					181.07
(b)	Rubbish 20%					45.27


J.E.


A.E.


E. Kumari