

ABSTRACT

Road name - Temporary Restoration of Road from Ramshalla to Sonhan via Kasnaraini

Block-DARBHANGA

RWD (W) DIVISION DARBHANGA -1

Road Actual Length - 3.00 KM

Efected Road Length 132.45 M.

S.No.	ITEM	UNIT	QUANTITY	RATE	AMOUNT (Rs)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I .	CUM	367.696 459.658	1867.76	68676820 858531
	Add G.S.T. 12 %				103024-82412=0
	Add 1 % Labor cess				8585 686820
	Seigniorage Fee @1063.00/cum x0.10				48862 3908620
	Total				1019001

Rs. 8,15,134=0 8,15,134=0

J.E.

Work Section Darbhanga-2

A.E.

Work Sub-Division
Darbhanga

E.E.

RWD Darbhanga -1

कार्यपालक अभियंता आर काठ वि कार्यप्रमाण फलपरास के पत्रांक 542-अनुं
दिनांक 07/04/2021 के द्वारा समाप्त जॉय प्राविदेन के आधार पर -

Post-Facto T/A for Rs. 8,15,134=0 (Rupees Eight Lacs fifteen
Thousand one hundred thirty four) only

09-04-21

Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2021

Detailed Estimate for Temporary Restoration of Ramshalla to Sonhan via Kasnaraini road for the year 2020 -21.

Block -Darbhanga

Total Restoration Length -132.45 M

R.W.D.[W] Division -Darbhanga -1

Length -3.00 km

S.N.	item	No.	Length (M)	Width(M)	Depth (M)(AV)	Quantity (cum)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I .					
	Chainage in M					
	200	1-	2.50	3.50	0.300	2.625
		1-	4.50	2.60	0.300	3.510
	2800	1-	3.50	1.20	0.225	0.945
		1-	0.60	0.60	0.225	0.081
		1-	30.00	(1.50+2.90)/2	1.250 ^{1.25}	82.500 ^{66.0}
		1-	14.00	(3.75+6.50)/2	1.800 ^{1.25}	129.150 ^{89.688}
		1-	30.00	(3.70+5.90)/2	1.500 ^{1.25}	216.000 ^{180.0}
		1-	2.25	1.50	0.900	3.038
		1-	6.00	1.30	0.300	2.340
		1-	18.10	1.30	0.225	5.294
	3000	1-	21.00	1.50	0.450	14.175
	Total Qty.					459.658

367.696

[Signature]
28/12/20
J.E.

[Signature]
28/12/20
A.E.

[Signature]
E.E.

RWD(W) Division Darbhanga -1