

ABSTRACT

Road name - Temporary Restoration of Road from To7,SH, Madhopur to Ketuka

Block-DARBHANGA

RWD (W) DIVISION DARBHANGA -1

Road Actual Length - 5.26 KM

Efected Road Length 29.50 M.

S.No.	ITEM	UNIT	QUANTITY	RATE	AMOUNT (Rs)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I .	CUM	96.023	1867.76	179348
	Add G.S.T. 12 %				21522
	Add 1 % Labor cess				1793
	Seigniorage Fee @1063.00/cum x0.10				10207
	Total				212870

Rs-2,12,870=00

J.E.

Work Section Darbhanga-2

A.E.

Work Sub-Division

Darbhang

E.E.

RWD Darbhanga -1

कार्यपालक अभियंता द्वारा कां वि० कार्यप्रमाणित पुलपरास के पत्रांक 542, अनु० 1 दिनांक 07/04/2021. को द्वारा समाप्त जॉन प्रतिवेदन के आधार पर -
Post-Facto T/A Rs-2,12,870=00 (Rupees Two Lacs Twelve Thous end Eight hundred seventy) only

09.04.21
Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2021

Detailed Estimate for Temporary Restoration of Ranipur T07,SH, Madhopur to Ketuka road for the year 2020 -21.

Block -Darbhanga

Total Restoration Length -29.5 M

R.W.D.[W] Division -Darbhanga -1

Length -5.26 km

S.N.	item	No.	Length (M)	Width(M)	Depth (M)(AV)	Quantity (cum)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I .					
	Chainage in M					
	Near SH	1	29.50	$(4.10+8.30)/2$	$(0.30+0.0.75)/2$	96.023
	Total Qty.					96.023

[Signature]
J.E.

[Signature]
28/12/20
A.E.

[Signature]
E.E.

RWD(W) Division Darbhanga -1