

ABSTRACT

Road Name- Temporary Restoration of Road from NH-57 Purana D.A.V.
School to Kabirchak

Block-DARBHANGA


RWD (W) DIVISION DARBHANGA -1

Road Actual Length - 3.100 KM


Efected Road Length - 407.10 M.

S.No.		UNIT	QUANTITY	RATE	AMOUNT (Rs)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I.	CUM	277.181 297.158	1867.76	517708.20 555020
	Add G.S.T. 12 %				66602 621252.00
	Add 1 % Labor cess				5550 5177.20
	Seigniorage Fee @1063.00/cum x0.10				31588 29464.00
					658760 614474.20


Rs. 6,14,474.20


J.E.

Work Section Darbhanga-2


A.E.


Work Sub-Division
Darbhanga


E.E.

RWD Darbhanga-1

कार्यपालक अभियंता द्वारा करे कि कार्य प्रमंडल - फुलपरास के पत्रांक 542 अन्तर्
दिनांक 07/04/2024 / के द्वारा समर्पित जॉय-प्रतिवेदन के आधार पर।

Post-Facto T/A for Rs- 6,14,474.20 (Rupees Six Lacs
Forteen thousand Four hundred Seventy four) only.



Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2024

Detailed Estimate for Temporary Restoration of NH-57 Purana D.A.V. School to Kabirchak road for the year 2020 -21.

Block -Darbhanga

Total Restoration Length -407.10 M

R.W.D.(W) Division -Darbhanga -1

Length -3.100 KM

S.N.	Item	No.	Length (M)	Width(M)	Depth (M)(AV)	Quantity (cum)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I.					
	Chainage in M					
	Part - II (East To West)					
	12 to 83	1	71.00	1.50 0.30	1.500 0.30	31.950
	103 -253	1	150.00	1.50 0.30	1.500 0.30	67.500
	278 - 316	1	38.00	(0.45+0.225)/2	1.250	16.031
	346 -359	1	13.00	0.75	0.250	2.438
	367 - 372	1	5.00	0.50	0.450	1.125
	North Side (Right Side)					0.000
	25 M to 262 M	1	237.00	0.25	(1.50+1.70)/2	94.800
	273 M to 337 M	1	64.00	0.30	(1.25+1.50)/2	26.400
	Part -(I) West towards east					
	North Side at 110 M to 175 M	1	65.00	1.45 1.00	0.225	21.200 14.625
	191-220	1	29.00	2.50 1.50	0.225	16.313 9.787
	South Side at 410M to 438 M	1	28.00	2.25 1.50	0.250	15.750 10.500
	438 M to 446 M	1	8.10	1.80 1.00	0.250	3.645 2.025
	Total Qty.					297.158 277.181

12/12/20

AE

EE

RWD(W) Division Darbhanga -1