

ABSTRACT

Road name - Temporary Restoration of Road from NH T02 to Ranna

Block-DARBHANGA

RWD (W) DIVISION DARBHANGA -1

Road Actual Length - 6.80KM

Efected Road Length 268.50 M.

S.No.	ITEM	UNIT	QUANTITY	RATE	AMOUNT (Rs)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I.	CUM	163.209	1867.76	304835
	Add G.S.T. 12 %				36580
	Add 1 % Labor cess				3048
	Seigniorage Fee @1063.00/cum x0.10				17349
	Total				361813

[Signature]
J.E.

Work Section Darbhanga-2

[Signature]
A.E.

Work Sub-Division
Darbhanga

~~Rs. 3,61,813~~ Rs. 3,61,813

[Signature]
E.E.

RWD Darbhanga -1

कार्यपालक अभियंता शा.का. वि. कार्य प्रमण्डल पुल परास के पत्रांक 542 अनु. 1
दिनांक 07/04/2021. के द्वारा समर्पित जॉय प्रानि व हेम के आधार पर —

Post-Facto T/A for Rs. 3,61,813 = (Rupees Three Lacs Sixty one
Thousand eight hundred thirteen) only

[Signature]
09.04.21

Superintending Engineer

RWD, Works Circle, Darbhanga
09/04/2021

p.p.w. (0/02)

Detailed Estimate for Temporary Restoration Of NH T02 to Ranna road for the year
2020 -21.

Block -Darbhanga

Total Restoration Length -268.50 M

R.W.D.[W] Division -Darbhanga -1

Length -6.80 km

S.N.	item	No.	Length (M)	Width(M)	Depth (M)(AV)	Quantity (cum)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I .					
	Chainage in M					
	570	1	5.20	1.80	0.150	1.404
		1	4.25	1.60	0.150	1.020
		1	2.20	3.70	0.150	1.221
	650	1	4.50	1.25	0.150	0.844
		1	2.10	1.80	0.150	0.567
	720	1	5.70	1.25	0.150	1.069
	1000	1	0.60	0.60	0.100	0.036
		1	0.30	0.40	0.100	0.012
		1	8.50	1.50	0.225	2.869
		1	4.50	0.75	0.150	0.506
		1	4.10	1.50	0.150	0.923
	1020	1	5.70	(0.6+1.25)/2	0.300	1.582
	1300	1	1.10	1.00	0.150	0.165
		1	7.00	(0.60+1.90)/2	0.300	1.575
		1	6.00	1.25	0.150	1.125
	1375	1	1.70	0.90	0.150	0.230
		1	5.70	3.75	0.150	3.206
		1	1.25	1.20	0.150	0.225
	1450	1	1.00	0.80	0.100	0.080
	1500	1	30.70	3.80	0.450	52.497
		1	5.00	1.00	0.300	1.500
	1575	1	35.00	(2.00+3.50)/2	0.300	28.875
	1650	1	1.60	1.90	0.225	0.684
	1980	1	8.70	(0.60+1.40)/2	0.225	1.958
		1	3.50	0.60	0.200	0.420
	2100	1	1.80	1.90	0.225	0.770
	2190	1	1.00	2.25	0.225	0.506
		1	0.60	0.60	0.150	0.054
	2225	1	5.80	0.70	0.225	0.914
		1	0.60	1.20	0.20	2.475
		1	0.60	0.70	0.150	0.063
	2525	1	1.80	1.50	0.900	2.430
		1	0.30	0.45	0.150	0.020
	2900	1	15.25	1.80	0.225	6.176
		1	3.50	0.80	0.225	0.630
		1	8.00	3.70	0.300	8.880
	3130	1	12.25	1.60	0.300	5.880
	3175	1	2.25	1.25	0.150	0.422
		1	0.70	0.45	0.225	0.071
	3200	1	4.25	3.70	0.250	3.931

page no. (2/02)

Block -Darbhanga

R.W.D.[W] Division -Darbhanga -1

Total Restoration Length -268.50 M

Length -6.80 km

S.N.	item	No.	Length (M)	Width(M)	Depth (M)(AV)	Quantity (cum)
	3290	1	1.70	0.80	0.200	0.272
		1	16.00	1.50	0.225	5.400
		1	4.00	3.70	0.225	3.330
	4250	1	4.40	1.50	0.750	4.950
		1	4.40	0.60	0.225	0.594
	4275	1	2.90	1.40	0.250	1.015
	4300	1	1.00	0.650	0.200	0.130
	4500	1	(3.5+1.25)/2	3.75	0.300	2.672
	4570	1	1.70	0.70	0.600	0.714
	4800	1	11.40	0.90	0.300	3.078
	4950	1	1.90	0.80	0.450	0.684
	5200	1	2.00	3.60	0.250	1.800
	5250	1	1.20	1.00	0.225	0.270
		1	1.30	1.25	0.300	0.488
	Total Qty.					163.209

[Signature]
25/12/20

J.E.

[Signature]
28/12/20

A.E.

[Signature]
E.E.

RWD(W) Division Darbhanga -1