

ABSTRACT

Road name - Temporary Restoration of Road from Sonki T03 To Ramberai

Block-DARBHANGA

RWD (W) DIVISION DARBHANGA -1

Road Actual Length - 7.80KM

Efected Road Length 312.30 M.

S.No.	ITEM	UNIT	QUANTITY	RATE	AMOUNT (Rs)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I .	CUM	441.952 527.252	1867.76	825460.20 984780
	Add G.S.T. 12 %				118174
	Add 1 % Labor cess				9848
	Seigniorage Fee @1063.00/cum x0.10				56047
	Total				1168849

99055=00

8255=00

46979=00

979749=00

28/12/20
J.E.

Work Section Darbhanga-2

28/12/20
A.E.

Work Sub-Division
Darbhanga

28/12/20
E.E.

RWD Darbhanga -1

कार्यपालक अभियंता आका वि कार्य समझल फुलफरास के पत्रांक 552 अनु
दिनांक 07/04/2021. के द्वारा समाप्त जाय प्रतिवेदन के आधार पर -
Post - Photo T/A Rs 9,79,749=00 (Rupees - Nine Lacs Seventy
nine thousand Seven hundred forty nine) only

09.04.21

Superintending Engineer

RWD, Works Circle, Darbhanga

09/04/2021

Detailed Estimate for Temporary Restoration Of Sonki T03 To Ramberai road for the year 2020 -21.

Block -Darbhanga

R.W.D.[W] Division -Darbhanga -1

Total Restoration Length -312.30 M

Length -7.80 km

S.N.	item	No.	Length (M)	Width(M)	Depth (M)(AV)	Quantity (cum)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I .					
	Chainage in M					
	240	1	2.10	1.80	(0.30+0.80)/2	2.079
	270	1	2.40	3.00	0.300	2.160
	300	1	3.60	2.90	0.900	9.396 ✓
	310	1	2.10	1.60	0.750	2.520
	338	1	2.80	2.20	(0.30+0.75)/2	6.468
		1	1.50	1.50	0.300	0.675
	342	1	35.00	3.80	(0.60+0.90)/2	99.750
	408	1	9.80	1.20	0.300	3.528
	519	1	3.60	1.70	0.150	0.918
	531	1	2.90	1.70	0.200	0.986
	534	1	1.10	0.60	0.150	0.099
	633	1	3.00	1.20	0.300	1.080
	636	1	2.50	3.90	0.600	5.850
	780	1	2.00	2.10	0.225	0.945 ✓
		1	2.50	0.60	0.150	0.225
	1100	1	2.10	1.80	(0.30+1.50)/2	3.402
	1150	1	2.80	1.60	0.225	1.008
	1245	1	6.00	2.70	0.300	4.860
	1257	1	3.50	2.40	0.225	1.890
	1276	1	40.00	1.20	0.225	10.800
	1715	1	14.50	3.60	0.225	11.745
	Beside	1	18.50	3.60	0.300	19.980
	2095	1	13.20	3.70	0.225	10.989
		1	3.30	1.60	0.225	1.188
	3750	1	3.30	1.60	0.225	1.188
	3755	1	3.10	2.60	0.225	1.814
	3759	1	4.60	2.60	0.300	3.588
		1	1.80	0.60	0.225	0.243
	3767	1	31.00	(3.50+5.75)/2	(0.90+1.50)/2	172.050 131.75
	3850	1	1.30	1.00	0.700	0.910
	3851	1	5.50	2.20	0.600	7.260
	3861	1	3.70	1.40	0.225	1.166
		1	4.00	2.90	0.300	3.480
	4000	1	4.60	3.90	0.900	16.146
		1	2.50	1.70	0.225	0.956
	5058	1	2.40	1.50	(0.30+1.50)/2	3.240
		1	2.30	1.80	(0.30+1.20)/2	3.105
	5135	1	3.40	3.00	0.300	3.060
	5200	1	1.50	1.50	0.450	1.013
		1	2.60	2.10	0.225	1.229

28/5/20

[Signature]

Block -Darbhanga
R.W.D.(W) Division -Darbhanga -1

Total Restoration Length -312.30 M
Length -7.80 km

S.N.	item	No.	Length (M)	Width(M)	Depth (M)(AV)	Quantity (cum)
		1	1.70	1.60	0.150	0.408
	6180	1	1.40	1.50	0.600	1.260
	6285	1	1.20	2.80	0.450	1.512
	Near culvert	1	2.10	3.00	0.750	4.725
	6464	1	1.50	2.90	0.600	2.610
	6550	1	50.00	$(0.60+1.90)/2$	1.500	93.750
	Total Qty.			$(0.30+1.00)$		527.252

48.75
441.952

[Handwritten signature]
A.E.

[Handwritten signature]
A.E.

[Handwritten signature]
E.E.

RWD(W) Division Darbhanga -1