FDR

DISTRICT :- **DARBHANGA**
BLOCK :- BAHADURPUR
Name of Raad :- Jiwanpatti T02 to Pachgachhiya.

Length of the Road 3.755 KM.
Effective Length 0.015 KM.

GENERAL ABSTRACT OF COST

Sl No.	Item of Work		Amount (in Rs.)
1	Cost for restoration		1,42,743.56
2	Add 12 % GST		17,129.23
3	Add 1 % Labour Cess		1,427.44
4	Seigniorage Fee	76.425 x 1063 x 10%	8,123.98
		Total cost:-	1,69,424.20

Say Rs. 1,69,424=00

5.12.2020.
Junior Engineer
Baheri

15/12/2020
Assistant Engineer
Baheri

Say. Rs. 1,69,424=00
16/12
Executive Engineer
V.D.(W) Division, Darbhanga-1

कार्यपालक अभियंता, ग्रा0 कार्य वि0, दरभंगा-मुजफ्फरपुर का पत्रांक 5423 दि0 07/04/2021 के द्वारा स्वीकृत प्राक्कलन के आलोक में-

Post-facto T/A for Rs. 1,69,424=00 (Rupees one lac sixty nine thousand four hundred twenty four) only

09.04.21
Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2021

Scanned with CamScanner

Detailed estimate for making moterable road.

Name of Raad :- Jiwanpatti T02 to Pachgachhiya.

BLOCK :- BAHADURPUR
DISTRICT :- DARBHANGA
R.W.D. Works Division Darbhanga-1

Sl. No.	Item	Unit	No.	Length	Breath		Av. Breadth	Depth / Height		Av. Depth / Height	Quantity	Rate	Amount
				(in m)	(in m)	(in m)	(in m)	(in m)	(in m)	(in m)	(in cum)	(in Rs.)	(in Rs.)
1	Labour and Placing Brick Bats with Light raming including cost of brick bats by tractor.	cum	1	10.00	3.00	4.50	3.75	1.50	2.50	2.00	75.000		
			1	2.00	0.50	1.00	0.75	0.35	0.65	0.50	0.750		
			1	2.50	0.40	0.80	0.60	0.30	0.60	0.45	0.675		
											76.425	1867.76	142743.56
												Total	142743.56

15.12.2020
Junior Engineer
Baheri

15/12/2020
Assistant Engineer
Baheri

Executive Engineer
R.W.D.(W) Division, Darbhanga-1

Scanned with CamScanner