

FDR

DISTRICT :- DARBHANGA

BLOCK :- BAHADURPUR

Name of Raad :- Hasanpur to Mekna Beda

Length of the Road:- 3.500 KM.
Effective Length 0.144 KM.

GENERAL ABSTRACT OF COST

Sl No.	Item of Work	Amount	
		(in Rs.)	
1	Cost for restoration	5,54,946.25	5,74,267.93
2	Add 12 % GST	66,593.55	68,912.15
3	Add 1 % Labour Cess	5,549.46	5,742.68
4	Seigniorage Fee 301.575 m ³ x Rs.1063.00 x 10 %	32,057.42	33,173.57
Total cost:-		6,59,146.68	6,82,096.34

Rs. 6,59,147 = 00.

15.12.2020
Junior Engineer
Bahadurpur

Assistant Engineer
Bahadurpur

Executive Engineer
R.W.D.(W) Division, Darbhanga-1

अर्थशास्त्र: अतिरिक्त, आठ करोड़, चार लाख-पचास हजार का प्राप्ति:- 54
— तिथि:- 07/04/2021 / के द्वारा समर्थित. और अतिरिक्त के अग्रार 42—

Fact-facto T/A फार्म 6,59,147=00 (Rupees Six thousand
— fifty nine thousand one hundred forty seven only.

09.04.21
Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2021

Detailed estimate for making moterale road.
 of Raad :- Hasanpur to Mekna Beda
 BAHADURUR
 CT :- DARBHANGA
 Works Division Darbhanga-1

Item	Unit	No	Length (m)	Breadth (m)	Depth / Height (m)	Quantity (in cum)	Rate (in Rs.)	Amount (in Rs.)
Labour and Placing Brick Bats with Light raming including cost of brick bats by tractor.		1	6.50	3.00	0.450	8.775		
		1	8.00	3.00	0.500	12.000		
		1	7.50	3.00	0.600	13.500		
		1	6.50	3.00	0.500	9.750		
		1	10.00	1.75	0.300	5.250		
		1	30.00	1.30	1.000	39.000	37.00	
		1	10.00	1.30	1.200	15.600		
		1	4.00	2.50	0.450	4.500		
		1	4.00	1.30	1.000	5.200		
		1	8.00	0.90	0.750	5.400		
		1	10.00	3.75	1.000	37.500		
		1	17.00	4.00	1.200	81.600		
		1	5.00	3.80	2.500	40.400	47.50	
		1	4.50	1.00	0.800	3.600		
		1	5.00	2.00	0.600	6.000		
		1	8.00	2.00	0.450	7.200	6.40	5,54,346.25
			201.575	m3		342.975	1840.16	511297.93
								Rs. 5,54,346.25

Bahamir
 15.12.2020.
 Junior Engineer
 Bahadurpur

7/15/2020
 Assistant Engineer
 Bahadurpur

19/12/20
 Executive Engineer
 R.W.D.(W) Division, Darbhanga-1