

Abstract of cost for Restoration work of road Pahadpur Tajpur Sugiya after flood 2020.

Sl. No.	Item of work	Unit	Quantity	Rate	Amount
1	Supplying & filling of brick bats with manual compactiondo....do all complete job as per direction of E/I.				
	(a) Bricks bat	cum	508.86	1546.00	786698.00
	(b) Rubbish	cum	127.21	742.00	94390.00
Total					881088.00
Add 1% labour Cess					8811.00
Add 12% GST					105731.00
Grand Total					995630.00
Say Rs					995620.00

Kannwarjan
05/04/21

J.E

Kumar
5.04.21
A.E.


6.4.21

यह प्राबलन अक्षीक्षण अनियंता कार्य अंचल सीतामढ़ी द्वारा
गठित नौचदल (कार्यपालक अनियंता सीतामढ़ी) के नौच प्रतिवेदन
254 / 29-1-21

Technically Approved for Rs 995620-00 (Rupees Nine
lakh Ninety five thousand Six hundred Twenty)
Only.


12/4/21

S.E.
R.W.D. (W) Bareilly
Sitamarhi

Detailed Estimate of Restoration work of road Pahadpur Tajpur Sugliya after flood 2020.

sl no. 1	Supplying & filling of brick bats with manual compactiondo....do all complete job as per direction of E/I.					
	from chainage M	to chainage M	length in M	width in M	depth in M	Quantity in CUM
1	80	92.00	12	3.35	0.20	8.04
2	133	148.00	15.00	3.35	0.15	7.54
3	340	352.00	12.00	3.35	0.30	12.06
4	460	473.00	13.00	3.35	0.30	13.07
5	490	496.00	6.00	3.35	0.30	6.03
6	600	606.00	6.00	1.52	0.30	2.74
7	820	836.20	16.20	3.35	0.30	16.28
8	1500	1521.50	21.50	3.35	0.30	21.61
9	2100	2150.00	50.00	3.35	0.30	50.25
10	2200	2255.00	55.00	3.35	0.15	27.64
11	2500	2603.00	103.00	2.13	0.45	98.73
12	4300	4380.00	80.00	3.05	0.60	146.40
13	4800	4830.00	30.00	3.05	0.25	22.88
14	5100	5107.60	7.60	1.22	0.60	5.56
15	5200	5244.00	44.00	3.05	0.45	60.39
16	5430	5465.00	35.00	3.50	0.45	55.13
17	5670	5687.00	17.00	3.35	0.40	22.78
18	5700	5713.00	13.00	3.50	0.15	6.83
19	6123	6140.00	17.00	3.35	0.30	17.09
20	6200	6208.00	8.00	3.35	0.20	5.36
21	6286	6295.00	9.00	3.00	0.30	8.10
22	6320	6336.00	16.00	3.00	0.45	21.60
	Total					636.07
(a)	Brick Bats 80%					508.86
(b)	Rubbish 20%					127.21

Hgwanjan
05/04/21
J.E.

(Signature)
05.04.21
A.E.

(Signature)
E.E.
05.04.21