

## TECHNICAL REPORT

Name of Work – FDR To Road From... Benugash REO road to kuchaha tk.

Head – FDR

Estimated cost – 6,71,898=00 Laes

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

**(A) Source of materials**

Brick Bats – Local Kiln

Fine sand – Local

Cement Bag – Local Market

Aggregate for G.S.B – Matigara (Silliguri) by road up to site.

Bamboo – Local


Earth – Private land from 1000m lead.

- (B) **Rate** - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST& 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

Sent  
25/12/20-  
J.E  
R.W.D  
Kishanganj-1

  
25/12/20  
A.E  
R.W.D  
Kishanganj-1

  
25/12  
E.E  
R.W.D  
Kishanganj-1

Inspection Report for flood damage work

Date:

1. Name of PIUs- Executive Engineer RWD works division  
Kishengang-1.

2. Name of Block/Road- Terhagachh/ Benugarh REO road to  
Kuchaha tk.

**A. For Road**

1. Damage Location/Chainage : 0.350 Km.  
2. Damage Length : 110 m.  
3. Nature of Damage : washed out flank damage.  
4. Details of Restoration :  
i Material being used in Restoration : Brick bats.  
ii Equipment/Tools being used in Restoration works: Tractor.  
iii Procedure taken up in Restoration works : manual.  
iv Restored Length : 110 m.

**B. For Bridge**

1. Damage Location/Chainage :  
2. Damage Length :  
3. Nature of Damage :  
4. Details of Restoration :  
i Material being used in Restoration :  
ii Equipment/Tools being used in Restoration works:  
iii Procedure taken up in Restoration works :  
iv Restored Length :

Signature of JE/AE/EE  
12/12/20

12/12/20

12/12

Signature  
12/12/20


(Name of Inspector)

Name of work :-

**Detailed Estimate**  
Benugarh REO Road to Kuchaha Tola

SI No	Item	No	Length (avg.)	Width (avg.)	Height (avg.)	Qty	Unit	Rate	Amount
1	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	3	30.00	4.20	0.60	226.80			
		1	20.00	4.20	0.60	50.40			
		Total				277.20	cum	2145.02	594600.00
TOTAL								594600.00	
							Add 12 % GST	Rs 71352.00	
							Add 1 % L. Ces	Rs 5946.00	
							Total Cost	Rs 671898.00	

Sony  
25/12/20-  
J.E  
RWD  
Kishanganj-1


  
25/12/20  
A.E  
R.W.D  
Kishanganj-1

C  
25/12  
E.E  
R.W.D  
Kishanganj - I

Technically approved for ₹ 6,71,898 = 00

(Rs. Six Lacs Seventy one thousand and eight hundred

and eighty only)

  
25/12/21